

Approved Tender Schedule

Construction of Addl. Class room , Boys & girls common room in Govt. (SSD) Higher Secondary school, MV-79		Amount per tender			Rs.2098042.00
		cost of tender paper			Rs. 6000 .00
		Earnest Money Deposit 1 %			Rs 20980 /-
		Class of Contractor			"B" & "C"
		Time of Completion			4 (Four) months
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Supplying & Filling in foundation and plinth with sand , well watered and rammed with all leads & lifts cost conveyance & royalty & all taxes of materials , cost of labour, T&P, Dewatering, shoring & shuttering required for the works etc. complete in all respect as directed by E-I-C.	6.27	cum	₹ 621.68	₹ 3,897.93
2	Providing , fitting & fixing of Al. door with OEL anodized Al. door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member and 12mm thick prelaminated board in bottom and top portion fixed on door frame by means of tapered clip No.4660 and frame to be completed bt means of jointing angle No.1855 including all cost of labour T & P hire charges of drilling machine labour charges etc complete.	80.80	Kg	439.80	₹ 35,535.84
3	Cement concrete of proporation (1:3:6) with using 40mm size HGHB metal free from weathered & skin with including cost ,conveyance, royalty & taxes of all materials, labour etc. Including curing, Dewatering if required in all respect including centering and shuttering etc. complete as per E-I-C.	1.20	cum	5190.23	₹ 6,228.28
4	WB CB brick masonry in CM (1:6) in Foundation with using good quality C.B. brick of 9" size having a crushing strength of not less than 35 kg/sqcm including splays cutting, circular moulding, chamfering and corblling and watering, curing etc. including cost, conveyance, royalty & all taxes of materials with cost of labour , T&P etc. complete required for the work complete in all respect as directed by E-I-C.	25.58	cum	4696.76	₹ 1,20,143.12
5	RCC M25 grade with 20 mm & down graded HGCB in plinth bend, Slab, Chajja including casting, Centering & shuttering, watering for 28 days including all labour, materials, T & P, taxes etc. as per E-I-C.				
c)	Beams & Columns .	21.43	cum	14397.15	₹ 3,08,530.92
d)	Lintel	0.69	cum	10777.97	₹ 7,436.80
e)	Roof Slab	26.19	cum	12239.03	₹ 3,20,540.20
6	Cement concrete of proporation(1:2:2) using 6 mm HGCB chips including cost, conveyance, royalty, taxes of all materials including curing & watering chipping of roof slab etc. Complete & including all labour, T&P. etc in all respect as directed by E-I-C. etc.complete.	104.36	sqm	329.72	₹ 34,409.58
7	Supplying,fitting and placing uncotaed HYSD bar reinforcement complete including labour charges for cutting, bending, binding & straightening and tying the grills & placing in position including cost of binding wire 18 to 20 guage as per drawing and technical spacification as directed by E-I-C. etc.	41.06	Qtl.	7759.43	₹ 3,18,602.20

8	Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778 as windows frame, section No.4095, 4096 & 9777, 3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including lucking arrangement including all fitting including cost of materials all taxes,cess labour, T&P but excluding cost of glass etc. complete and as per direction of Engineer-in-charge.	303.01	Kg	610.95	₹ 1,85,123.96
9	Supplying, fitting, fixing of Vitrified tiles in floors tread or steps/dadOs and landing on 20mm thick bed of cement mortar 1:1(1cement: 1 Sand) jointed with neat cement slurry mixed with pigments to match the shades or the tiles including rubbing and polishing etc.,complete as per direction of Engineer-in-charge.	326.96	sqm	1419.31	₹ 4,64,057.60
10	12mm thick cement plaster in C.M.(1:6) finished smooth to outer side brickwork after racking out the joints including watering & curing with cost, conveyance, royalty of all materials, labour with T&P required for the work including all taxes etc. complete in all respect in all floors as directed by E-I-C.	167.25	sqm	153.68	₹ 25,702.98
11	16mm thick cement plaster in C.M.(1:6) finished smooth to inner side brickwork after racking out the joints including watering & curing with cost, conveyance, royalty of all materials, labour with T&P required for the work including all taxes etc. complete in all respect in all floors as directed by E-I-C.	144.18	sqm	218.88	₹ 31,558.12
12	Painting two coats of enamel painting over Doors, windows & grills including cost of paint & Primer of approved make & shade etc. complete as directed by E-I-C.	68.39	sqm	148.82	₹ 10,177.80
13	Finishing with distemping two coats with approved make & shade of distemper to inner side surface over one coat water bound approved primer over cement plastering including cost of all material, cost, T&P required for the work etc. complete as directed by E-I-C.	644.23	sqm	261.00	₹ 1,68,144.03
14	Finishing with weather seal paint two coats with approved make & shade of weather seal paint to outer side surface over one coat of primer over cement plastering including cost of all material, cost, T&P required for the work etc. complete as directed by E-I-C.	167.25	sqm	267.62	₹ 44,759.45
15	Dismantling and removing lime concrete flooring 7.5 cm to 10 cm thick including stacking the useful materials for reuse and removing the debris within 50m lead	30.60	sqm	118.49	₹ 3,625.79
16	Dismantling and removing cement concrete including stacking the useful materials for reuse and removing the debris within 50m lead	0.79	Cum	641.15	₹ 507.79
17	Dismantling and removing 2.5 cm thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead	89.64	sqm	86.18	₹ 7,725.18
18	Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height	290.72	sqm	4.59	₹ 1,334.40
Total					2098041.96

Or Say

₹ 20,98,042.00

Rupees(Twenty lakh Ninety Eight Thousand and Forty Two) or
(Eighteen nos. of item only)

Tender schedule for the project "Construction of Addl. Class room , Boys & girls common room in Govt. (SSD) Higher Secondary school, MV-79" for cost of Rs. 20,98,042.00 (Rupees Twenty Lakhs Ninety Eight Thousand and Forty Two) Approved.

No of corrections :-
No of over writings :-
No. of Interpolation :-

R.L. 09/05/23
Addl. P.D. (Tech.)
D.R.D.A., malkangiri.

My quoted rate is % Excess % Less or Schedule rate.

(Both in figure and words) over the above amount put to tender.

Signature of Contractor

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

9.05.2023