

Approved Tender Schedule

**Const. Of Community Center at Annapurna Temple
Mathili**

Amount put to tender - Rs.1463179.00 /-
 cost of tender paper with VAT 5% - Rs.6000.00
 Earnest Money Deposit 2% of Est. Cost
 Class of Contractor "C" & "D"
 Time of Completion 3 (Three) months

Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Supplying all labour, T&P etc. and earth work in excavation of foundations in hard soil including dressing and levelling of the bed and depositing the soil within 50M initial lead & 1.50M initial lift and including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	68.70	100 cum	206.77	14204.00
2	Supplying all materials, labour, T&P etc. and filling in foundatin and plinths with sand well watered and rammed including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	38.98	cum	547.07	21327.00
3	Supplying all materials, labour, T&P etc. and providing Cement concrete (1:4:8)in foundation and up to lowest bed level using hard black hand broken granite metal of size 4cm of approved quality from approved quarry as per approved design including hoisting laying, compacting concrete in layers not exceeding 6" thick watering curing finished smooth providing grooves or beads where necessary including cost, conveyance royalties and taxes of all materials with labour and T&P required for the work complete in all respects including dewatering if required i all complete as per specification and direction of Engineer-in-charge.	44.03	cum	4901.92	215845.00
4	Supplying all materials, labour, T&P etc. and providing RCC work (1:1.5:3) in plinth bend, Slab, Chajja etc. Having a minium compressive strength(in work test) of 150.00 kg/sqcm in 15 c.m. Cubes at 28 days as per I.S. 456 and 516 using 12 mm. to 20 mm. size(20 mm. not to exceed 25 %) HBCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction of concrete, watering & curing for 04 weeks including centering & shuuttering and finishing the exposed surfaces smooth with cost, conveyance, royalty & taxes of all materials and labour with T&P required except cost for reinforcement for the work etc. complete as directed by EIC.				
a)	Column Base	7.79	cum	7706.87	60021.00
b)	Plinth Band	5.16	cum	8089.00	41708.00
c)	Beams & Columns .	6.34	cum	14546.50	92224.00
d)	Lintel	2.36	cum	11040.93	26091.00
e)	Roof Slab	13.21	cum	12575.92	166120.00
6	Supplying all materials, labour, T&P etc. and cutting, straightening, coiled or bent up uncoated HYSD bars bending, binding, welding, and jointing if necessary and tying the grills and placing in proper position as required for RCC works including cost, conveyance, taxes of HYSD bars and binding wires of 18 to 20 gauge required for the work (Payment will made on weight of HYSD bars only and no separate payment will be made towards the weight of binding wires) as directed by EIC	33.57	Qtl.	9583.51	321709.00
7	Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in F&P using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per. sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of woks with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc., complete in all respect.	27.74	cum	5368.27	148939.00

8	Supplying all materials, labour, T&P etc. and fitting and fixing of Vetrified tiles in floors of size 600mm x 600mm of approved make conforming to IS:13755 laid on 20mm thick C.M(1:4) and filling joints with white cement including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC	89.22	sqm	1108.61	98904.00
9	Supplying, fitting, fixing of Ceramic tiles in floors tread or steps and landing on 25mm thick bed of cement mortar 1:1 (Cement: 1 sand) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing etc., complete as per direction of Engineer-in-charge.	97.87	sqm.	782.01	76536.00
10	Supplying, fitting, fixing of M.S. door shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	7.74	sqm	7460.13	57741.00
11	Supplying, fitting, fixing of M.S windows shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	2.52	sqm	5383.41	13566.00
12	Supplying all materials, labour, T&P etc. and providing 12mm ($\frac{1}{2}$ " thick Cement Plaster (1:6) finished smooth to outside brick walls after raking out the joint including, watering curing with cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	110.91	sqm.	153.68	17045.00
13	Supplying all materials, labour, T&P etc. and providing 16mm ($\frac{3}{4}$ " thick Cement Plaster (1:6) finished smooth to brick walls after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	96.90	sqm.	218.88	21209.00
14	Supplying all materials, labour, T&P etc. and providing 20mm thick Cement Plaster (1:6) finished smooth to stone work after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	22.83	sqm.	230.49	5261.00
15	Supplying all materials, labour, T&P etc. and providing wall putty including cost of wall putty and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	123.81	sqm.	95.20	11786.00
16	Supplying all materials, labour, T&P etc. and providing Painting two coats to the MS door, window & grill works over a coat of priming including cost of primer and paint and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	27.77	sqm.	146.69	4073.00
17	Supplying all materials, labour, T&P etc. and providing distempering two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	178.68	sqm.	65.30	11668.00

17	Supplying all materials, labour, T&P etc. and providing weather coat two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	133.74	sqm.	84.32	11277.00
18	Supplying all materials, labour, T&P etc. and providing Cement washing 1 (one) coat with any approved water proofing cement paint with brush to wall surface after cleaning surface including cost of paint, watering, and curing cost T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and	241.71	sqm.	15.94	3852.00
19	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete.	447.86	cum	49.28	22073.00
19 (Nineteen items) only					1463179.00

Tender schedule for the project = Const. Of Community Center at Annapura Temple Mathili for Rs. 1463179/- Rupees(Fourteen Lakhs Sixty three Thousand one Hundred seventy nine only)

No of corrections :-

No of over writings :-

No. of Interpolation :-


Addl. P.D.(Tech.)
D.R.D.A., Malkangiri.

My quoted rate is % Excess % Less or Schedi
(Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

Signature of Contractor

Approved Tender Schedule

Repair & Renovation of Varudei Temple at Bara		Amount put to tender - Rs.1067885.00 /-			
		cost of tender paper with VAT-8% - Rs.4200.00			
		Earnest Money Deposit 2 %		Est Cost "C" & "D"	
		Class of Contractor		Time of Completion 3 (Three) months	
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Supplying all labour, T&P etc. and earth work in excavation of foundations in hard soil including dressing and levelling of the bed and depositing the soil within 50M initial lead & 1.50M initial lift and including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	40.49	100 cum	206.77	8372.00
2	Supplying all materials, labour, T&P etc. and filling in foundation and plinths with sand well watered and rammed including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	25.39	cum	547.07	13889.00
3	Supplying all materials, labour, T&P etc. and providing Cement concrete (1:4:8) in foundation and up to lowest bed level using hard black hand broken granite metal of size 4cm of approved quality from approved quarry as per approved design including hoisting laying, compacting concrete in layers not exceeding 6" thick watering curing finished smooth providing grooves or beads where necessary including cost, conveyance royalties and taxes of all materials with labour and T&P required for the work complete in all respects including dewatering if required in all complete as per specification and direction of Engineer-in-charge.	32.31	cum	4901.92	158395.00
4	Supplying all materials, labour, T&P etc. and providing RCC work (1:1.5:3) in plinth bend, Slab, Chajja etc. Having a minimum compressive strength (in work test) of 150.00 kg/sqcm in 15 c.m. Cubes at 28 days as per I.S. 456 and 516 using 12 mm. to 20 mm. size (20 mm. not to exceed 25 %) HBCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction of concrete, watering & curing for 04 weeks including centering & shuttering and finishing the exposed surfaces smooth with cost, conveyance, royalty & taxes of all materials and labour with T&P required except cost for reinforcement for the work etc. complete as directed by EIC.				
a)	Column Base	3.60	cum	7706.87	27745.00
b)	Plinth Band	3.15	cum	8089.00	25507.00
c)	Beams & Columns	4.79	cum	14546.50	69674.00
d)	Lintel	1.44	cum	11040.93	15884.00
e)	Roof Slab	10.78	cum	12575.92	135564.00
6	Supplying all materials, labour, T&P etc. and cutting, straightening, coiled or bent up uncoated HYSD bars bending, binding, welding, and jointing if necessary and tying the grills and placing in proper position as required for RCC works including cost, conveyance, taxes of HYSD bars and binding wires of 18 to 20 gauge required for the work (Payment will be made on weight of HYSD bars only and no separate payment will be made towards the weight of binding wires) as directed by EIC	22.86	Qtl.	9583.51	219088.00
7	Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in F&P using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect	22.31	cum	5368.27	119762.00

8	Supplying all materials, labour, T&P etc. and fitting and fixing of Vetrified tiles in floors of size 600mm x 600mm of approved make conforming to IS:13755 laid on 20mm thick C.M(1:4) and filling joints with white cement including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC	68.88	sqm	1108.61	76361.00
9	Supplying, fitting, fixing of Ceramic tiles in floors tread or steps and landing on 25mm thick bed of cement mortar 1:1 (Cement: Isand) jointed with neat cement slurry mixed with pigments to match the shades or the tiles including rubbing and polishing etc., complete as per direction of Engineer-in-charge.	42.87	sqm.	782.01	33525.00
10	Supplying, fitting, fixing of M.S. door shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	7.74	sqm	7460.13	57741.00
11	Supplying, fitting, fixing of M.S windows shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	2.52	sqm	5383.41	13566.00
12	Supplying all materials, labour, T&P etc. and providing 12mm (½") thick Cement Plaster (1:6) finished smooth to outside brick walls after raking out the joint including, watering curing with cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	98.91	sqm.	153.68	15201.00
13	Supplying all materials, labour, T&P etc. and providing 16mm (¾") thick Cement Plaster (1:6) finished smooth to brick walls after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	85.20	sqm.	218.88	18648.00
14	Supplying all materials, labour, T&P etc. and providing 20mm thick Cement Plaster (1:6) finished smooth to stone work after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	19.97	sqm.	230.49	4602.00
15	Supplying all materials, labour, T&P etc. and providing wall putty including cost of wall putty and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	101.11	sqm.	95.20	9625.00
16	Supplying all materials, labour, T&P etc. and providing Painting two coats to the MS door, window & grill works over a coat of priming including cost of primer and paint and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	27.77	sqm.	146.69	4073.00
17	Supplying all materials, labour, T&P etc. and providing distempering two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	154.98	sqm.	65.30	10120.00

17	Supplying all materials, labour, T&P etc. and providing weather coat two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	118.88	sqm.	84.32	10024.00
18	Supplying all materials, labour, T&P etc. and providing Cement washing 1 (one) coat with any approved water proofing cement paint with brush to wall surface after cleaning surface including cost of paint, watering, and curing cost T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-	215.15	sqm.	15.94	3429.00
19	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete.	346.76	cum	49.28	17090.00
18 (Eighteen items) only					1067885.00

Tender schedule for the project "Repair & Renovation of Varudei Temple at Bara
for Rs. 1067885 /- Rupees(Ten Lakhs Sisty Seven Thousand Eight Hundred Eighty Five only)

No of corrections :-
No of over writings :-
No. of Interpolation :-


Addl. P.D. (Tech.)
D.R.D.A., Malkangiri.

My quoted rate is % Excess % Less or Schedule rate.
(Both in figure and words) over the above amount put to tender.

- Note:**
1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
 2. Strike out which are not applicable.
 3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
 4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
 5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
 6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

Signature of Contractor

Approved Tender Schedule

Const. Of Community Center at Mauli Devi Asthana Pujariguda		Amount put to tender - Rs.1463179.00 /- cost of tender paper with VAT 5% - Rs.6000.00 Earnest Money Deposit 2 % of Est. Cost Class of Contractor "C" & "D" Time of Completion 3 (Three) months			
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Supplying all labour, T&P etc. and earth work in excavation of foundations in hard soil including dressing and levelling of the bed and depositing the soil within 50M initial lead & 1.50M initial lift and including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge	68.70	100 cum	206.77	14204.00
2	Supplying all materials, labour, T&P etc. and filling in foundatin and plinths with sand well watered and rammed including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	38.98	cum	547.07	21327.00
3	Supplying all materials, labour, T&P etc. and providing Cement concrete (1:4:8)in foundation and up to lowest bed level using hard black hand broken granite metal of size 4cm of approved quality from approved quarry as per approved design including hoisting laying, compacting concrete in layers not exceeding 6" thick watering curing finished smooth providing grooves or beads where necessary including cost, conveyance royalties and taxes of all materials with labour and T&P required for the work complete in all respects including dewatering if required i all complete as per specification and direction of Engineer-in-charge.	44.03	cum	4901.92	215845.00
4	Supplying all materials, labour, T&P etc. and providing RCC work (1:1.5:3) in plinth bend, Slab, Chajja etc. Having a minium compressive strength(in work test) of 150.00 kg/sqcm in 15 c.m. Cubes at 28 days as per I.S. 456 and 516 using 12 mm. to 20 mm. size(20 mm. not to exceed 25 %) HBCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction of concrete, watering & curing for 04 weeks including centering & shuuttering and finshing the exposed surfaces smooth with cost, conveyance, royalty & taxes of all materials and labour with T&P required except cost for reinforcement for the work etc. complete as directed by EIC.				
a)	Column Base	7.79	cum	7706.87	60021.00
b)	Plinth Band	5.16	cum	8089.00	41708.00
c)	Beams & Columns .	6.34	cum	14546.50	92224.00
d)	Lintel	2.36	cum	11040.93	26091.00
e)	Roof Slab	13.21	cum	12575.92	166120.00
6	Supplying all materials, labour, T&P etc. and cutting, straightening, coiled or bent up uncoated HYSD bars bending, binding, welding, and jointing if necessary and tying the grills and placing in proper position as required for RCC works including cost, conveyance, taxes of HYSD bars and binding wires of 18 to 20 gauge required for the work (Payment will made on weight of HYSD bars only and no separate payment will be made towards the weight of binding wires) as directed by EIC	33.57	Qtl.	9583.51	321709.00
7	Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in F&P using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per. sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of woks with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc., complete in all respect.	27.74	cum	5368.27	148939.00

8	Supplying all materials, labour, T&P etc. and fitting and fixing of Vetrified tiles in floors of size 600mm x 600mm of approved make conforming to IS:13755 laid on 20mm thick C.M(1:4) and filling joints with white cement including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC	89.22	sqm	1108.61	98904.00
9	Supplying, fitting, fixing of Ceramic tiles in floors tread or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement: 1 sand) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing etc., complete as per direction of Engineer-in-charge.	97.87	sqm.	782.01	76536.00
10	Supplying, fitting, fixing of M.S. door shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	7.74	sqm	7460.13	57741.00
11	Supplying, fitting, fixing of M.S windows shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	2.52	sqm	5383.41	13566.00
12	Supplying all materials, labour, T&P etc. and providing 12mm (½") thick Cement Plaster (1:6) finished smooth to outside brick walls after raking out the joint including, watering curing with cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	110.91	sqm.	153.68	17045.00
13	Supplying all materials, labour, T&P etc. and providing 16mm (¾") thick Cement Plaster (1:6) finished smooth to brick walls after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	96.90	sqm.	218.88	21209.00
14	Supplying all materials, labour, T&P etc. and providing 20mm thick Cement Plaster (1:6) finished smooth to stone work after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	22.83	sqm.	230.49	5261.00
15	Supplying all materials, labour, T&P etc. and providing wall putty including cost of wall putty and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	123.81	sqm.	95.20	11786.00
16	Supplying all materials, labour, T&P etc. and providing Painting two coats to the MS door, window & grill works over a coat of priming including cost of primer and paint and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	27.77	sqm.	146.69	4073.00
17	Supplying all materials, labour, T&P etc. and providing distempering two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	178.68	sqm.	65.30	11668.00

17	Supplying all materials, labour, T&P etc. and providing weather coat two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	133.74	sqm.	84.32	11277.00
18	Supplying all materials, labour, T&P etc. and providing Cement washing 1 (one)coat with any approved water proofing cement paint with brush to wall surface after cleaning surface including cost of paint, watering, and curing cost T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and	241.71	sqm.	15.94	3852.00
19	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete.	447.86	cum	49.28	22073.00
19 (Nineteen items) only					1463179.00

Tender schedule for the project = Const. Of Community Center at Mauli Devi Asthana Pujariguda for Rs. 1463179/- Rupees(Fourteen Lakhs Sixty three Thousand one Hundred seventy nine only)

No of corrections :-
No of over writings :-
No. of Interpolation :-


06/07/23
Addl. P.D.(Tech.)
D.R.D.A., Malkangiri.

My quoted rate is % Excess % Less or Schedi
(Both in figure and words) over the above amount put to tender.

Note:

Signature of Contractor

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

Approved Tender Schedule

Const. Of Community Center at Rama Lingeswar Temple Mathili

Amount put to tender - Rs.1463179.00 /-
 Cost of tender paper with VAT 5% - Rs.6000.00
 Earnest Money Deposit 2 % of Est. Cost
 Class of Contractor "C" & "D"
 Time of Completion 3 (Three) months


Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Supplying all labour, T&P etc. and earth work in excavation of foundations in hard soil including dressing and levelling of the bed and depositing the soil within 50M initial lead & 1.50M initial lift and including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge	68.70	100 cum	206.77	14204.00
2	Supplying all materials, labour, T&P etc. and filling in foundation and plinths with sand well watered and rammed including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	38.98	cum	547.07	21327.00
3	Supplying all materials, labour, T&P etc. and providing Cement concrete (1:4:8) in foundation and up to lowest bed level using hard black hand broken granite metal of size 4cm of approved quality from approved quarry as per approved design including hoisting laying, compacting concrete in layers not exceeding 6" thick watering curing finished smooth providing grooves or beads where necessary including cost, conveyance royalties and taxes of all materials with labour and T&P required for the work complete in all respects including dewatering if required i all complete as per specification and direction of Engineer-in-charge.	44.03	cum	4901.92	215845.00
4	Supplying all materials, labour, T&P etc. and providing RCC work (1:1.5:3) in plinth bend, Slab, Chajja etc. Having a minium compressive strength(in work test) of 150.00 kg/sqcm in 15 c.m. Cubes at 28 days as per I.S. 456 and 516 using 12 mm. to 20 mm. size(20 mm. not to exceed 25 %) HBCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction of concrete, watering & curing for 04 weeks including centering & shuuttering and finshing the exposed surfaces smooth with cost, conveyance, royalty & taxes of all materials and labour with T&P required except cost for reinforcement for the work etc. complete as directed by EIC.				
a)	Column Base	7.79	cum	7706.87	60021.00
b)	Plinth Band	5.16	cum	8089.00	41708.00
c)	Beams & Columns .	6.34	cum	14546.50	92224.00
d)	Lintel	2.36	cum	11040.93	26091.00
e)	Roof Slab	13.21	cum	12575.92	166120.00
6	Supplying all materials, labour, T&P etc. and cutting, straightening, coiled or bent up uncoated HYSD bars bending, binding, welding, and jointing if necessary and tying the grills and placing in proper position as required for RCC works including cost, conveyance, taxes of HYSD bars and binding wires of 18 to 20 gauge required for the work (Payment will made on weight of HYSD bars only and no separate payment will be made towards the weight of binding wires) as directed by EIC	33.57	Qtl.	9583.51	321709.00
7	Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in F&P using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of woks with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc., complete in all respect.	27.74	cum	5368.27	148939.00

8	Supplying all materials, labour, T&P etc. and fitting and fixing of Vetrified tiles in floors of size 600mm x 600mm of approved make conforming to IS:13755 laid on 20mm thick C.M(1:4) and filling joints with white cement including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC	89.22	sqm	1108.61	98904.00
9	Supplying, fitting, fixing of Ceramic tiles in floors tread or steps and landing on 25mm thick bed of cement mortar 1:1 (Cement: 1 sand) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing etc., complete as per direction of Engineer-in-charge.	97.87	sqm.	782.01	76536.00
10	Supplying, fitting, fixing of M.S. door shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	7.74	sqm	7460.13	57741.00
11	Supplying, fitting, fixing of M.S windows shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	2.52	sqm	5383.41	13566.00
12	Supplying all materials, labour, T&P etc. and providing 12mm ($\frac{1}{2}$ ") thick Cement Plaster (1:6) finished smooth to outside brick walls after raking out the joint including, watering curing with cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	110.91	sqm.	153.68	17045.00
13	Supplying all materials, labour, T&P etc. and providing 16mm ($\frac{3}{4}$ ") thick Cement Plaster (1:6) finished smooth to brick walls after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	96.90	sqm.	218.88	21209.00
14	Supplying all materials, labour, T&P etc. and providing 20mm thick Cement Plaster (1:6) finished smooth to stone work after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	22.83	sqm.	230.49	5261.00
15	Supplying all materials, labour, T&P etc. and providing wall putty including cost of wall putty and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	123.81	sqm.	95.20	11786.00
16	Supplying all materials, labour, T&P etc. and providing Painting two coats to the MS door, window & grill works over a coat of priming including cost of primer and paint and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	27.77	sqm.	146.69	4073.00
17	Supplying all materials, labour, T&P etc. and providing distempering two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	178.68	sqm.	65.30	11668.00

17	Supplying all materials, labour, T&P etc. and providing weather coat two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	133.74	sqm.	84.32	11277.00
18	Supplying all materials, labour, T&P etc. and providing Cement washing 1 (one) coat with any approved water proofing cement paint with brush to wall surface after cleaning surface including cost of paint, watering, and curing cost T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and	241.71	sqm.	15.94	3852.00
19	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete.	447.86	cum	49.28	22073.00
19 (Nineteen items) only					1463179.00

Tender schedule for the project = Const. Of Community Center at Rama Lingeswar Temple Mathili
for Rs. 1463179/- Rupees(Fourteen Lakhs Sixty three Thousand one Hundred seventy nine only)

No of corrections :-
No of over writings :-
No. of Interpolation :-


Addl. P.D.(Tech.)
D.R.D.A., Malkangiri.

My quoted rate is % Excess % Less or Schedi
(Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

Signature of Contractor

Approved Tender Schedule


Sl. No.		Item of Work	Amount put to tender - Rs.1463179.00 /- cost of tender paper with VAT 5% - Rs.6000.00 Earnest Money Deposit 2 % of Est. Cost Class of Contractor "C" & "D" Time of Completion 3 (Three) months			
			Quantity	Unit	Rate	Amount
1		Supplying all labour, T&P etc. and earth work in excavation of foundations in hard soil including dressing and levelling of the bed and depositing the soil within 50M initial lead & 1.50M initial lift and including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	68.70	100 cum	206.77	14204.00
2		Supplying all materials, labour, T&P etc. and filling in foundation and plinths with sand well watered and rammed including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	38.98	cum	547.07	21327.00
3		Supplying all materials, labour, T&P etc. and providing Cement concrete (1:4:8) in foundation and up to lowest bed level using hard black hand broken granite metal of size 4cm of approved quality from approved quarry as per approved design including hoisting laying, compacting concrete in layers not exceeding 6" thick watering curing finished smooth providing grooves or beads where necessary including cost, conveyance royalties and taxes of all materials with labour and T&P required for the work complete in all respects including dewatering if required i all complete as per specification and direction of Engineer-in-charge.	44.03	cum	4901.92	215845.00
4		Supplying all materials, labour, T&P etc. and providing RCC work (1:1.5:3) in plinth bend, Slab, Chajja etc. Having a minimum compressive strength(in work test) of 150.00 kg/sqcm in 15 c.m. Cubes at 28 days as per I.S. 456 and 516 using 12 mm. to 20 mm. size(20 mm. not to exceed 25 %) HBCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction of concrete, watering & curing for 04 weeks including centering & shuttering and finishing the exposed surfaces smooth with cost, conveyance, royalty & taxes of all materials and labour with T&P required except cost for reinforcement for the work etc. complete as directed by EIC.				
a)		Column Base	7.79	cum	7706.87	60021.00
b)		Plinth Band	5.16	cum	8089.00	41708.00
c)		Beams & Columns .	6.34	cum	14546.50	92224.00
d)		Lintel	2.36	cum	11040.93	26091.00
e)		Roof Slab	13.21	cum	12575.92	166120.00
6		Supplying all materials, labour, T&P etc. and cutting, straightening, coiled or bent up uncoated HYSD bars bending, binding, welding, and jointing if necessary and tying the grills and placing in proper position as required for RCC works including cost, conveyance, taxes of HYSD bars and binding wires of 18 to 20 gauge required for the work (Payment will made on weight of HYSD bars only and no separate payment will be made towards the weight of binding wires) as directed by EIC	33.57	Qtl.	9583.51	321709.00
7		Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in F&P using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per. sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc., complete in all respect.	27.74	cum	5368.27	148939.00

8	Supplying all materials, labour, T&P etc. and fitting and fixing of Vetrified tiles in floors of size 600mm x 600mm of approved make conforming to IS:13755 laid on 20mm thick C.M(1:4) and filling joints with white cement including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC	89.22	sqm	1108.61	98904.00
9	Supplying, fitting, fixing of Ceramic tiles in floors tread or steps and landing on 25mm thick bed of cement mortar 1:1 (Cement: Sand) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing etc., complete as per direction of Engineer-in-charge.	97.87	sqm.	782.01	76536.00
10	Supplying, fitting, fixing of M.S. door shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	7.74	sqm	7460.13	57741.00
11	Supplying, fitting, fixing of M.S windows shutters in proper position including making holes in walls, RCC structures and wood work etc., making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc., complete in all respects as per direction of EIC.	2.52	sqm	5383.41	13566.00
12	Supplying all materials, labour, T&P etc. and providing 12mm (½") thick Cement Plaster (1:6) finished smooth to outside brick walls after raking out the joint including, watering curing with cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	110.91	sqm.	153.68	17045.00
13	Supplying all materials, labour, T&P etc. and providing 16mm (¾") thick Cement Plaster (1:6) finished smooth to brick walls after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	96.90	sqm.	218.88	21209.00
14	Supplying all materials, labour, T&P etc. and providing 20mm thick Cement Plaster (1:6) finished smooth to stone work after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour, T&P required for the work etc., complete in all respects as per direction of EIC.	22.83	sqm.	230.49	5261.00
15	Supplying all materials, labour, T&P etc. and providing wall putty including cost of wall putty and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	123.81	sqm.	95.20	11786.00
16	Supplying all materials, labour, T&P etc. and providing Painting two coats to the MS door, window & grill works over a coat of priming including cost of primer and paint and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	27.77	sqm.	146.69	4073.00
17	Supplying all materials, labour, T&P etc. and providing distempering two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	178.68	sqm.	65.30	11668.00

17	Supplying all materials, labour, T&P etc. and providing weather coat two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material , cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	133.74	sqm.	84.32	11277.00
18	Supplying all materials, labour, T&P etc. and providing Cement washing 1 (one)coat with any approved water proofing cement paint with brush to wall surface after cleaning surface including cost of paint ,watering, and curing cost T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-	241.71	sqm.	15.94	3852.00
19	Excavation, loading, unloading and carriage by mechanical means of all kinds of soil, including stoney earth, gravel and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineerin-charge within an initial lead of 1km from the place of excavation complete.	447.86	cum	49.28	22073.00
19 (Nineteen items) only					1463179.00

Tender schedule for the project = Const. Of Community Center at Radhakrushna Temple Udulibeda
for Rs. 1463179/- Rupees(Fourteen Lakhs Sixty three Thousand one Hundred seventy nine only)

No of corrections :-
No of over writings :-
No. of Interpolation :-


Addl. P.D.(Tech.)
D.R.D.A., Malkangiri.

My quoted rate is % Excess % Less or Sched
(Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

Signature of Contractor