

Approved Tender Schedule

Project No-01

Renovation & Development of Maa Mutyaluma Pitha Manyamkonda Village		Amount put to tender			Rs. 1676487.00
		cost of tender paper			Rs. 6000.00
		Earnest Money Deposit 1 %			Rs 16767/-
		Class of Contractor			C & D
		Time of Completion			4 (Four) months
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	E/W excavation of foundation in hard soil within initial lead and lift including fine dressing of trenches and levelling of bed etc complete	23.47	cum	₹ 206.77	₹ 4,852.89
2	Supplying & Filling in foundation and plinth with sand , well watered and rammed with all leads & lifts cost conveyance & royalty & all taxes of materials , cost of labour, T&P, Dewatering, shoring & shuttering required for the works etc. complete in all respect as directed by E-I-C.	17.76	cum	₹ 621.68	₹ 11,041.04
3	Cement concrete of proparation (1:3:6) with using 40mm size HGHB metal free from weathered & skin with including cost ,conveyance, royalty & taxes of all materials, labour etc. Including curing, Dewatering if required in all respect including centering and shuttering etc. complete as per E-I-C.	24.01	cum	5054.62	₹ 1,21,361.43
4	Cement concrete of proparation (1:2:4) with using 12mm size HGCB chips free from weathered & skin with including cost ,conveyance, royalty & taxes of all materials, labour etc. Including curing, Dewatering if required in all respect including centering and shuttering etc. complete as per E-I-C.	12.90	cum	6862.64	₹ 88,528.06
5	Earthwork in hard soil within initial lead and lift including rough dressing and breaking clods etc complete	130.95	cum	212.69	₹ 27,851.76
6	Supplying, fitting , fixing of Chequered tiles in floors tread or steps and landing on 20mm thick bed of cement mortar 1:1(1cement: 1 Sand) jointed with neat cement slurry mixed with pigments to match the shades or the tiles including rubbing and polishing etc.,complete as per direction of Engineer-in-charge.	243.05	sqm	974.48	₹ 2,36,847.36
7	Providing and laying of heavy duty made hydraulicpressed and mechanically compacted precastinterlocking paver of 250mmx100mmx80mm thick coral, zigzag or any other shape as per direction of EIC-in-charge including all cost etc complete	538.80	sqm	1105.97	₹ 5,95,896.64
8	Supplying, fitting , fixing of Stainless steel of 304 grade as per design specification buffing polishing etc .,complete as per direction of Engineer-in-charge including all cost .	75.00	mtr	3521.36	₹ 2,64,102.00
9	RCC M25 grade with 20 mm & down graded HGCBC in plinth bend, Slab, Chajja including casting, Centering & shuttering, watering for 28 days including all labour, materials, T &P, taxes etc. as per E-I-C.				
a)	Column Base	4.27	cum	8454.64	₹ 36,101.31
b)	Plinthbend	1.41	cum	8924.07	₹ 12,582.94
c)	Column & Beam	10.06	cum	14262.45	₹ 1,43,480.25
10	Supplying,fitting and placing uncotaed HYSD bar reinforcement complete including labour charges for cutting, bending, binding & straightening and tying the grills & placing in position including cost of binding wire 18 to 20 guage as per drawing and technical spacification as directed by E-I-C. etc.	6.52	Qtl.	7753.44	₹ 50,552.43

11	Supplying, fitting, fixing up MS Grill Gate including all fitting including cost of materials all taxes, cess labour, T&P etc. complete and as per direction of Engineer-in-charge.	494.55	Kg	100.00	₹ 49,455.00
12	6mm thick cement plaster in C.M.(1:4) over concrete surface after deep cheeping including watering & curing with cost, conveyance, royalty of all materials, labour with T&P required for the work including all taxes etc. complete in all respect in all floors as directed by E-I-C.	70.03	sqm	157.43	₹ 11,024.82
13	Painting two coats of with any approve enamel painting over a coat of priming over MS grills including cost of paint & Primer of approved make & shade including papering polishing the surface with cost, conveyance, taxes of all materials etc. complete as directed by E-I-C.	31.79	sqm	148.82	₹ 4,730.99
14	Finishing with distemping (emulsion) two coats with approved make & shade of distemper to inner side surface over one coat water bound approved primer over cement plastering including cost of all material, cost, T&P required for the work etc. complete as directed by E-I-C.	70.03	sqm	261.00	₹ 18,277.83
Total					1676686.73

Or Say

₹ 16,76,687.00

Rupees(Sixteen Lakh Seventysix Thousand Six Hundred Eightyseven) only
(Fourteen nos. of item only)

Tender schedule for the project "Renovation & Development of Maa Mutyalama Pitha Manyamkonda Village" for cost of Rs. 16,76,887.00 (Rupees sixteen Lakh Seventy six Thousand Eight Hundred Eightyseven) Approved.

No of corrections :-

No of over writings :-

No. of Interpolation :-

Chit
06/07/23
Addl. P.D.(Tech.)
D.R.D.A., malkangiri.

My quoted rate is % Excess % Less or Schedule rate.

(Both in figure and words) over the above amount put to tender.

Signature of Contractor

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.