

**Approved Tender Schedule**

Project No-06

Repair & Renovation of Sri Tarakeswar Mandir at MV-79	Amount put to tender	Rs.1257074.00
	cost of tender paper	Rs. 6000 .00
	Earnest Money Deposit 1 %	Rs 12571 /-
	Class of Contractor	"C" & "D"
	Time of Completion	4 (Four) months

Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Eartwork excavation of foundation in hardsoil within initial lead and lift including fine dressing of trenches and levelling of bed etc complete as per directed by EIC.	62.90	cum	₹ 206.77	₹ 13,005.83
2	Supplying & Filling in foundation and plinth with sand , well watered and rammed with all leads & lifts cost conveyance & royalty & all taxes of materials , cost of labour, T&P, Dewatering, shorring & shuttering required for the works etc. complete in all respect as directed by E-I-C.	58.47	cum	₹ 621.68	₹ 36,349.63
3	Cement concrete of proporation (1:3:6) with using 40mm size HGCB metal free from weathered & skin with including cost ,conveyance, royalty & taxes of all materials, labour etc. Including curing, Dewatering if required in all respect including centering and shuttering etc. complete as per E-I-C.	144.04	cum	5002.40	₹ 7,20,545.70
4	Cement concrete of proporation (1:2:4) with using 12mm size HGCB metal free from weathered & skin with including cost ,conveyance, royalty & taxes of all materials, labour etc. Including curing, Dewatering if required in all respect including centering and shuttering etc. complete as per E-I-C.	50.91	cum	6788.97	₹ 3,45,643.44
5	Rigid and smooth centering and shuttering for RCC work with false work and dismantling after casting including cost of materials ,T&P, etc complete as per EIC	228.80	sqm	93.89	₹ 21,482.03
6	Supplying,fitting and placing uncotaed HYSD bar reinforcement complete including labour charges for cutting, bending, binding & straightening and tying the grills & placing in position including cost of binding wire 18 to 20 guage as per drawing and technical spacification as directed by E-I-C. etc.	6.43	Qtl.	7729.49	₹ 49,700.62
7	Earthwork in hardsoil within initial lead and lift including rough dressing and braking clods etc complete as directed by EIC	330.75	cum	212.69	₹ 70,347.22
	<b>Total</b>				<b>1257074.46</b>

Or Say

₹ 12,57,074.00

Rupees(Twelve Lakh Fiftyseven Thousand Seventyfour) only

(Seven nos. of item only)

Tender schedule for the project "Repair & Renovation of Sri Tarakeswar Mandir at MV-79" for cost of Rs. 1257074.00 ( Rupees Twelve Lakh Fiftyseven Thousand Seventyfour) Approved.

No of corrections :-

No of over writings :-

No. of Interpolation :-

  
 Addl. P.D.(Tech.)  
 D.R.D.A., malkangiri.

My quoted rate is ..... % Excess ..... % Less or Schedule rate.

(Both in figure and words) over the above amount put to tender.

Signature of Contractor

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.