

TENDER SCHEDULE**NAME OF THE WORK : Repair & Renovation of Village Temple at Bhejengiwada****SCHEME :Mukhyamantri Swatantra Sahayata (2023-24)****Class of Contractor : C & D****Amount put to Tender (Approx.) : Rs.1326458.00****G.P Bhejengiwada****Cost of Tender Paper : Rs.6000****BLOCK : KALIMELA****Time for completion of the work:****Earnest Money Deposit 1% : Rs.13264.00****03 (three)Months**

SI No	Items of work	Quantity	Unit	Rates in Rs	Amount in Rs
1	2	3	4	5	6
1	Earth work in excavation in hard soil or gravelly soil within 50m initial lead & 1.50m initial lift including rough dressing & breaking clods to maximum 5cm to 7cm laying in layer not exceeding 0.30m in depth and as per the direction of the Engineer -in-charge.	39.68	100 Cum	23973.36	9513.00
2	Filling foundation & Plinth with sand watered & rammed including cost, carriage and royalty etc comp.	49.18	1 Cum	460.82	22663.00
3	Cement Concrete (1:3:6) with 4 cm size hard granite metal including cost, carriage, royalties and taxes of all materials etc.	29.11	1Cum	5313.24	154669.00
4	R.C.C. work of M-20 grade with 20mm and down grade black h.g.(c.b.)chips including hoisting and laying with all cost, TC&Royalty etc.(Data for 15 cum)	33.64	1 Cum	5388.35	181264.00
5	Rigid smooth centering & shuttering to R.C.C'work including falsework & dismantling them after casting including cost of materials comp.				
	Plinth bend & Mass concrete	125.20	1sqm	78.43	9819.00
	Lintel	6.72	1sqm	227.54	1529.00
	Slab & Chaja	107.43	1sqm	384.90	41350.00
	Beams & columns	52.26	1sqm	793.09	41444.00
6	W.B.C.B. Brick masonry in C.M. (1:6) with all finishing, curing in superstructure etc. complete.	30.41	1 Cum	5010.78	152378.00
7	20 mm thick CP in CM (1:6) over stone masonry	13.72	1sqm	254.16	3487.00
8	12mm.thick Cement Plaster in C.M.(1:6) including cost, carriage & royalty etc. complete.	49.77	1Sqm	169.86	8454.00
9	16 mm. thick cement plaster in cement mortar(1:6) over brick masonry with all finishing curing per Sqm.	41.28	1Sqm	243.81	10065.00
10	Supplying & fixing of MS door and windows welded with standard approved MS grill with approved standard MS section including all etc. comp.	120.19	1Kg	100.00	12019.00

11	Labour for strangthing, cutting, benidng & binding the M.S. Road inlcuding cost of binding wire including cost of binding wire but exculuding cost of binding wire but including cost of MS Rod.	33.64	1Qntl	7094.64	238664.00
12	Supplying fitting and fixing vitrified tile in floor of size 600mmx600mm of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS:15477 of 3 mm thick bed and filling joints with white cement of approved quility including cost of all materials,labour T&P etc required for the work all complete as per direction of Engineer-in-Charge.(For repair work only)Data for 10.00sq	99.38	1Sqm	995.00	98888.00
13	Finishing wall with water proofing cement paints of approved shasle on new work 2 coats to give anshade etc. including cost of shade etc.	91.05	1Sqm	41.58	3786.00
14	Distempering Two coat with any approved distemper over new plaster surface etc.	192.92	1Sqm	78.90	15221.00
15	Painting two coat with aproved paint over D/S,W/S etc.	7.18	1Sqm	173.40	1245.00
16	Dome Design Cost				200000.00
17	Shree DADHIBAMAN Statue Cost (Height-5')				120000.00
18	Information Pillar				3000.00
				Total	1326458.00

Rupees Thirteen Lakhs Twenty Six thousand Four Hundred Fifty Eight

Note-

The Amount put to Tender is exclusive of 12% GST .The intnding bidders should offer their rates which shall exclusive of GST applicable as per norms.GST applicatble on works contract shall be paid over the bill amount at the time of payment of billon submission of Tax invoice

Tender schedule for the project " Repair & Renovation of Village Temple at Bhejengiwada" .
of Bhejengiwada G.P under Kalimela Block for Rs 13,30,53.00 (Rupees Thirteen Lakhs Thirty Thousand Fifty Three only)

No of correction.
No of Overwriting.
No of Interpolation.

mit
06/07/23
Addl. P.D.(Tech.)
DRDA Malkangiri.

My Quoted rate is _____ % excess _____ % less
(Both in figures and words) over the above amount put to tender

Signature of the Contractor

Note :

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the liable for rejection
2. Strike out which are not applicable.

3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less upto one decimal point only. If he writes the percentage excess or less upto two or more decimal points the first two decimal points shall only be considered without rounding off.

(18 (Eighteen) Items Only .)



Block Development Officer
Kalimela Block .