


TENDER SCHEDULE

Name of the Project :- Construction ACR Building at BAPANPALLY KGBV UPS, Block- PODIA					
Cost of Tender Paper : Rs.6000/-			Class of Contract D / C		
Amount put to Tender (Approx.) : 10,03,153.00			At : Malkangiri		
Cost of Tender Paper : Rs.6000/-			Dist. : Malkangiri		
Earnest Money : 1% of the Estimated Cost			Time for completion of the work : 4 (Four) Months		
SL. NO.	ITEM OF WORKS	QUANTITY	UNIT	RATE in Rs	AMOUNT in Rs
1	2	3	4	5	6
1	Earth work in excavation of foundation trenches in ordinary soil except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away from the site with all leads and lifts. T & P shoring and shuttering if required etc. complete as directed by engineer-in charge.	Cum	34.86	206.80	7209.05
2	Supplying and filling in foundation and ditches with sand well watered and rammed in layers not exceeding 23 cm in depth with all lead and lift including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all labour, sundries. T & P required for the work etc complete in all respect as per direction of Engineer incharge.	Cum	21.96	513.00	11265.48
3	Providing & laying plain cement concrete 1:4:8 (1 cement 4 coarse and 8 graded stone aggregate of 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundries, T & P required for the work complete including dewatering if required as per instruction of Engineer-in- charge.	Cum	27.53	4789.60	131857.69
4	Providing and laying C.B brick masonry work in super structure thoroughly soaked in water with cement mortar (1:6) including necessary scaffolding, racking out joints, curing, etc. complete. As per specification and direction of the Engineer-in -charge.	Cum	21.26	4659.70	99065.22
5	i. Providing, lifting hoisting laying Reinforced cement concrete of M20 grade in column footings, as per approved designs and drawings having a minimum compressive strength (in work test) 200 Kg./ Square cm in 15cm. Cubes at 28 days after mixing and tests conducted in accordance with I.S. 416 using 12mm to 20 mm size black hard crusher broken granite stone chips of approved quality from approved quarry washed and cleaned (20mm size not to exceeds 25%) to be mixed in concrete mixture with ordinary portland cement (OPC) including hoisting, lowering laying and compacting concrete by using vibrators, watering and curing for 28 days centering and shuttering and finishing the exposed surface smooth providing grooves or beads wherever necessary including cost conveyance, loading and unloading royalties and taxes of all materials and cost of all labours sundries, T & P required for the work complete in all respect excluding cost and conveyance of HYSD/MS steel and binding wires, and labour charges for straightening, cutting, bending etc of M.S. rods of for steel and binding				
a	Column Base	Cum	6.40	6312.20	40398.08
b	Column Up to Plinth	Cum	1.66	14058.20	23336.61
c	Grade Beam	Cum	2.22	8524.70	18924.83
d	Lintel Beam	Cum	1.34	13345.00	17882.30

e		Cum	3.05	14058.20	42877.51
	Ring Beam				
f		Cum	0.54	16727.80	9033.01
	Chajja				
g		Cum	8.44	12690.30	107106.13
	Roof Slab				
6	Cutting, bending binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, tools etc. complete.	Qntl	20.84	9260.00	192936.27
7	25 thick Cement concrete (1:2:2) for grading concrete over roof slab with 6 mm C.B.H.G. Chips	Cum	66.19	321.80	21299.94
8	Supplying, fitting and fixing of M.S Door, M. S grill for windows and ventilators including cost of labour, material transportation etc. complete.				
	A) Door	Kg	192.07	110.30	21184.88
	B) Window	Kg	167.25	106.80	17862.30
	C) Labour for Fitting fixing of doors/windows etc complete.	Sqm	9.66	568.60	5492.68
9	12mm thick cement plaster in cement mortar (1:6) over the out side wall surface including necessary scaffolding, curring, etc. completed.	Sqm	84.98	151.00	12831.98
10	16mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curring, etc. completed.	Sqm	120.74	215.70	26043.62
11	Fixing of Virified tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment o match the shades of the tiles including rubbing and polishing complete excluding cost of precast TILES	Sqm	61.38	1429.20	87724.30
12	Fixing Chequered tiles in floors on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shades of the tiles incl. rubbing and polishing complete incl. cost of tile etc all complete.	Sqm	6.95	1429.20	9932.94
13	20 mm thick cement plaster (1:6) over Stone work with cost of all materials and all labour etc.complete.	Sqm	23.81	226.70	5397.73
14	Priming 1 coat with any approved primer including cost per 1 Sqm. (Plastered surface)	Sqm	123.18	62.70	7723.39

15	Weather Coat 2 coats to the inner walls & ceiling complete in all respect.	Sqm	123.18	75.80	9337.04
16	Distempering two coat to walls with distemper of approved shade on new work to give an even shade including cost.per 1 Sqm.	Sqm	177.36	72.50	12858.60
17	Providing two coat of enamel paint over the grill work including cost of all materials and labour etc. complete	Sqm	23.97	150.60	3609.88
18	Stainless Steel Railing for the Ramp including all costs complete with approved gauge and Quality	Sqm	5.57	3257.00	18141.49
19	Provision for Green Board in the Class Room				5000.00
20	Provision for Electrification and Installation of fittings as requirement including all costs complete.				20000.00
21	Provision for BALA Painting				5000.00
22	Provision for Contingencies				11820.00
				TOTAL	1003152.95
				Or Say	1003153.00

Cost of the Project- 10,03,153.00	(Rupees Ten Lakh Three Thousand One Hundred Fifty Three) only		
Total No. of Items -22 (Twenty Two)			
Tender Schedule for the Project-"Construction of Additional Class Room Building at Bapanpally KGBV UPS", Podia for the cost Rs 10,03,153.00 (Rupees Ten Lakh Three Thousand One Hundred Fifty Three) is Approved.			


 Addl. P.D (Tech.)
 ZP , Malkangiri  12.06.23

My Quoted rate is _____ % excess _____ % less
 (Both in figures and words) over the amount put to tender

Signature of the Contractor

Note :

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less upto one decimal point only. If he writes the percentage excess or less upto two or more decimal points the first two decimal point shall only be considered without rounding off.