

TENDER SCHEDULE

NAME OF THE WORK : Construction of Road with Cuvert from Gorasetu Chawk to COB Gorasetu

SCHEME : SCA / 2020-21

CLASS OF CONTRACTOR : 'D' & 'C'

AMOUNT PUT TO TENDER (APPROX.) :Rs.17,85,714.00

At: Chittrakonda Block

COST OF TENDER PAPER : Rs.6,000.00

DIST : MALKANGIRI

EARNEST MONEY 1% : Rs17,858.00

**TIME OF COMPLETION OF THE WORK :
6 (Months)**

Sl. No.	Items of Work	Unit	Quantity	Rate per Unit	Amount	
1	Earth work excavation in foundation in hard soil with initial lead and lift etc. complete.	Cum.	68.410	188.79	Rs.	12915.00
2	Filling foundation and plinth with sand well waterd and rammed etc. complete including all cost and conveyance.	Cum.	14.49	1007.75	Rs.	14602.00
3	Providing and laying P.C.C bed concrete (1:3:6) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete including Centering.	Cum.	73.04	5254.78	Rs.	383809.00
4	R.R.H.G stone masonry in sand grouted in Foundation and Plinth including all cost, conveyance etc. complete.	Cum.	5.12	2543.26	Rs.	13022.00
5	R.C.C M-20 with 20 mm & downgrade size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete (excluding the cost of Steel but including the cost of centering and shuttering)	Cum.	5.06	10089.16	Rs.	51051.00
6	Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of blnding wire, steel, labour, tools etc. complete.	Qntl.	6.07	7863.67	Rs.	47732.00
7	Cement concrete (1:2:4) with 12mm size HGHB Chips including all cost, conveyance etc. complete.	Cum.	19.39	6651.81	Rs.	128979.00
8	Earth work in Hard Soil with in intial lead and lift including rough dressing and breaking clods.	Cum.	696.00	192.33	Rs.	133862.00
9	Labour for laying sub-base in layers not exceeding 100mm watering and compacting to the required density in O.M.C with PRR but excluding cost and conveyance of sub base materials.	Cum.	528.80	703.96	Rs.	372254.00
10	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel roller 8-10 tonnes in stages to proper grade and camber.	Cum.	240.00	2594.12	Rs.	622589.00
11	Cost of Sign Board (1.50Mtr x 1.80Mtr)	No	1.00	4899.00	Rs.	4899.00
Total					Rs.	1785714.00

(Rupees Seventeen lakhs Eighty Five Thousand Seven Hundred Fourteen) only.

Tender schedule for the project: Constn of Road with Culvert from Gorasetu Chack to COB Gorasetu of Panasput GP under Chittrakonda Block technically approved for Rs.17,85,714 /- (Rupees Seventeen lakhs Eighty Five Thousand Seven Hundred Fourteen) only.

No of corrections :-
No of over writings :-
No. of Interpolator :-


Actg. PD (Technical)
OPDPA, Malkangiri

My quoted rate is % Excess % Less
(Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.