

TENDER SCHEDULE

Name of the Project :- Construction ACR Building at Govt. UGHS Telerai, Block- Kalimela					
Cost of Tender Paper : Rs.6000/-			Class of Contractor D / C		
Amount put to Tender (Approx.) : 1133059.00			At : Govt. UGHS TELERAI		
Cost of Tender Paper : Rs.6000/-			Dist. : Malkangiri		
Earnest Money : 1% of the Estimate Cost			Time for completion of the work : 4 (Four) Months		
SL	ITEM OF WORKS	QUANTIT	UNIT	RATE in Rs	AMOUNT in Rs
1	2	3	4	5	6
1	Earth work in excavation of foundation trenches in ordinary soil except sheet rock and boulders (requiring blasting) including dressing and leveling the bed upto the required depth and depositing the excavated materials away from the site with all leads and lifts. T & P shoring and shuttering if required etc. complete as directed by engineer-in charge.	Cum	35.66	269.70	9617.50
2	Supplying and filling in foundation and ditches with sand well watered and rammed in layers not exceeding 23 cm in depth with all lead and lift including cost, conveyance, loading and unloading, royalties and taxes of all materials and cost of all labour, sundries. T & P required for the work etc complete in all respect as per direction of Engineer incharge.	Cum	43.72	639.50	27958.94
3	Providing & laying plain cement concrete 1:4:8 (1 cement:4 coarse and 8 graded stone aggregate fo 40 mm nominal size) in foundation and pinth including cost of hoisting, lowering laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15cm thick including cost. Conveyance, loading and unloading, royalties and taxes all materials and cost of all labours, sundnes, T & P required for the work complete including dewatering if required as epr instrucion of Engineer-in- charge.	Cum	29.08	5556.60	161585.93
4	Providing and laying C.B brick masonry work in super structure thoroughly soked in water with cement mortora (1:6) including necessary scaffolding, racking out joints, curing, etc. complete. As per specification and direction of the Engineer-in -charge.	Cum	21.11	5308.90	112070.88
5	i Providing, lifting hoisting laying Reinforced cement concrete of M20 grade in column footings, as per approved designs and drawings having a munimum compressive strength (in work test) 200 Kg./ Square cm in 15cm. Cubes at 28 days after mixing and tests conducted in accordance with I.S. 416 using 12mm to 20 mm size black hard crusher broken granite stone ships of approved quality from approved quarry washed and cleaned (20mm size not to exceeds 25%) to be mixed in concrete mixture with ordinary protland cement (OPC) including noisting, lowering lying an dcompacting concrete by susing vibrators, watering and curing for 28 days centering and shuttering and finishing the exposed surface smooth proving grooves or beads wherever necessary including cost conveyance, loading and unloading royalties and taxes of all materials and cost of all labours sunones, T & P required fo rthe work ect complete in all respect excluding cost and conveyance of HYS/MS steel and binding wires, and labour charges for straightaining, cutting, bending etc of M.S. rods of for steel and binding				

a	Column Base	Cum	7.45	6687.90	49824.86
b	Column Up to Plinth	Cum	1.89	15811.40	29883.55
c	Grade Beam	Cum	2.30	7554.00	17374.20
d	Lintel Beam	Cum	1.39	14297.30	19873.25
e	Ring Beam	Cum	3.97	15811.40	62771.28
f	Chajja	Cum	0.64	18385.10	11766.48
g	Roof Slab	Cum	9.47	13859.50	131249.47
6	Cutting, bending binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, tools etc.	Qntl	24.40	9091.60	221825.95
7	2.5mm thick Cement concrete 1:2:2 for grading concrete over roof slab with 6 mm C.B.H.G. Chips	Cum	74.47	394.00	29341.18
8	Supplying, fitting and fixing of M.S Door, M. S grill for windows and ventilators including cost of labour, material transportation etc.				
	a) Door	Kg	146.87	116.50	17110.82
	b) Window	Kg	223.13	116.50	25994.06
9	Labour for Fitting fixing of doors/windows etc complete.	Sqm	10.50	724.40	7606.20
10	12mm thick cement plaster in cement mortar (1:6) over the out side wall surface including necessary scaffolding, curring, etc. completed.	Sqm	95.32	189.30	18044.08
11	16mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curring, etc. completed.	Sqm	127.18	272.30	34631.11
12	Fixing of Virfified tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1cement : 1sand) jointed with neat cement slury mixed with pigment o match the shades of the tiles	Sqm	69.00	1260.90	87002.10
13	Priming 1 coat with any approved primer including cost per 1 Sqm. (Plastered surface)	Sqm	237.97	79.00	18799.63
14	Weather Coat 2 coats to the inner walls & ceiling complete in all respect.	Sqm	110.79	95.70	10602.60
15	Distempering two coat to walls with distemper of approved shade on new work to give an even shade including cost.per 1 Sqm.	Sqm	195.55	86.40	16895.52
16	Providing two coat of enamel paint over the grill work including cost of all materials and labour etc. complete	Sqm	26.59	181.40	4823.43
17	Fixing Chequred tiles in floors on 25 mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to	Sqm	6.95	921.70	6405.82
				TOTAL	1133058.78
				Or Say	1133059.00

Cost of the Project

Total No. of Items -17 Nos

(Rupees Eleven lakh thirty Three Thousand Fifty Nine only)

[Signature]
 Superintending Engineer, RWS&S-cum
 Addl. P.D. (Tech)
 Dir. Project Director (Tech)
 DDA P. Mahangiri
 Palkangiri.

My Quoted rate is _____ % excess _____ % less
 (Both in figures and words) over the amount put to tender . . .

Signature of the Contractor

Note :

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding
2. Strike out which are not applicable
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less upto one decimal point only. If he writes the percentage excess or less upto two or more decimal points the first two decimal point shall only be considered without rounding off.