

**OFFICE OF THE PANCHAYAT SAMITI,
KHAIRPUT**

No. 6216 /VI-84/2024(Dev.)

Dated: 06-11-2024

TENDER CALL NOTICE NO – 02/ 2024-25

The Block Development Officer, Khairput invites sealed percentage rate tenders on behalf of Governor of Odisha from Registered & eligible registered contractors of Odisha State PWD / CPWD having experience in construction of road and building works in conformity with detailed tender call notice for execution of the following works on drawl of agreement in Panchayat Samiti contract forms of Govt .of Odisha, the details are mentioned below.

Sl. No .	Name of the G.P.	Name of the Work	Name of the scheme	Tender value in Rs.	Cost of Tender Paper (non-refundable) in Rs.	E.M.D in Rs.	Time of Completion of the work in months.	Class of Contractor.
01.	K-Gumma	Constn.of Multipurpose Class Room at Darwin Degree College, K-Gumma	Infrastruc ture Development	4189552/-	6,000/-	41896/-	06(Six)	B
02	K-Gumma	Constn.of Additional Class Room with Toilet at Darwin Degree College, K-Gumma	Infrastruc ture Development	3607627/-	6,000/-	36076/-	06(Six)	B & C
03	K-Gumma	Constn.of 50 Seated Girls Hostel Building at Darwin Degree College, K-Gumma	Infrastruc ture Development	2518574/-	6,000/-	25186/-	06(Six)	B & C
04	K-Gumma	Constn.of Dinning Hall at Darwin Degree College, K-Gumma	Infrastruc ture Development	1677034/-	6,000/-	16770/-	06(Six)	C & D

Sale of Tender Paper: The Tender paper documents can be seen from the Govt. website <https://malkangiri.odisha.gov.in> only from dt.**07.11.2024 to 16.11.2024 (up to 5-00PM)**. No tender paper will be sold by the Block Office, Khairput or any other offices. The Interest bidders will download the bid documents from the web site only i.e. <https://malkangiri.odisha.gov.in>

Date of receipt of Tender Paper: Tender Paper complete in shape will be reached from **dt.07.11.2024 to 16.11.2024** in office hour(working days only) in the office of the Block Development Officer, Khairput through **REGISTERED POST/SPEED POST** only. Tender received by post after stipulated date & time mentioned above will not be considered. Further no tender papers will be received by hand or by Courier Service.

Date of Opening of Tender Papers : The tender shall be opened on **dt.18.11.2024** at **11-00 A.M.** in the office of the Block Development Officer, Khairput in presence of the bidders or their authorized representatives having written authorization for the purpose along with all relevant original documents.

Cost of Tender Paper : A non-refundable processing fees for Rs.6000/- (Rupees Six Thousand) only in shape of Demand Draft drawn in any Nationalized Banks/ Schedule Banks in favour of the Block Development Officer, Khairput payable at Khairput has to be submitted along with Expression of Interest response. Bids received without or with inadequate EOI processing fees shall be liable to get rejected.

The undersigned reserves the right to reject any or all the tenders without assigning any reason thereof. The detailed information/corrigendum on tender call notice can be available in the District website <https://malkangiri.odisha.gov.in> only.

N.B.:- All should go through the terms and conditions of Tender Call Notice and Detail Tender Call Notice before submission of Tender Papers.

1. The following documents should be furnished with the Tender Papers failing which the tender is liable for rejection.

- a. Earnest money deposit pledged in favour of Block Development Officer, Khairput
- b. Attested copy of valid Contractor Registration Certificate.
- c. Attested copy of valid PAN Card and GST Registration certificates.
- d. Attested copy of valid labour license if any. **(Labour license will be submitted for individual works at the time of agreement for successful bidders).**
- e. Original money receipt granted by B.D.O, Khairput towards cost of tender paper.
- f. The bidders have to produce an original affidavit in support of the authenticity of documents including EMD etc., attached with the tender paper.
- g. The Engineer Contractors desirous of availing exemption of EMD should submit an original affidavit as regards the fact of availing award of work without submission of EMD/ISD during the current financial year, otherwise their tender paper will be liable for rejection.

- h. The SC/ST contractors desirous of availing preference should submit an original affidavit in support of caste certificate and attested copy of caste certificate; otherwise their tender will be liable for rejection.
- i. Joint venture consortium agreements are not allowed to participate in tender.
- j. A critical analysis and working procedure should be submitted along with bid paper if the quoted amount is less than the estimate cost by more than 10% for examination by the committee.
- k. The name of the project for which tender paper is filled should be written in **CAPITAL LETTERS** on the cover in which all the required papers are kept and sealed.

Additional Performance Security Deposit: Additional performance Security shall be deposited by the successful bidders, where the bid amount is seriously unbalanced i.e less than the estimated cost put to tender. In such an event, the bidders who have quoted less bid price/rates than the estimated cost put to tender minus the quoted amount as A.P.S.D. in shape of N.S.C. / K.V.P./ Demand Draft / T.D.R. duly pledged in favour of Block Development Officer, Khairput will be deposited at the time of agreement at the following range/rate.

Sl. No.	Range of difference between the estimated cost put to tender and Bid amount	Additional Performance Security to be deposited by the Successful bidder
a.	Below 5%	No Additional Performance Security
b.	From 5% and above and below 10%	50% of (Difference between estimated cost put to tender and Bid amount).
c.	From 10% and above	150% of (Difference between estimated cost put to tender and Bid amount).

Shortfall if any required document(s), draft(s) and EMD, tender paper is liable for rejection.

2. If the date of sale, receipt and opening of the tender as specified above happens to be holiday(s), then the process of sale, receipt and opening whatsoever will be shifted to immediate next working day at the same specified time and venue respectively without further notice. However, date of tender paper opening may be postponed as per the convenience of the authority by intimating all the concerned tenderers through notice affixing to Notice Board at Panchayat Samiti, Khairput only.
3. The details of successful bidders against each work will be displayed in the notice board. The successful bidder will collect the letter of acceptance from the office of the undersigned within seven days from the date of declaration of list of successful bidders on the notice board in order to avoid postal delay for early execution of the work. No further claim will be entertained for non-receipt of acceptance letter.
4. The EMD amount is to be forfeited if the tender backs out from the offer acceptance of tender by the competent authority.
5. The appropriate GST shall be paid extra on Tender bid amount of the said projects as and when applicable as per the Govt. norms.
6. The Tender Paper shall not be sold to the defaulting contractors.


7. Each sealed cover should contain tender paper for one work only & its related documents and the name of work are written in CAPITAL LETTERS on the body of the cover, otherwise it will be rejected.
8. The undersigned reserves the right to reject any or all the tenders without assigning any reason thereof.


Block Development Officer
Khairput

Memo No. 6217/2024.

Dated: 06-11-2024.

Copy forwarded to the Deputy Director(Advertisement), Information & Public Relation Department, Odisha, Near State Guest House, Bhubaneswar-751001.


Block Development Officer
Khairput

Memo No. 6218/2024.

Dated: 06-11-2024.

Copy submitted to the Collector-cum-Chief Executive Officer, Zilla Parishad, Malkangiri for favour of kind information and necessary action.


Block Development Officer
Khairput

Memo No. 6219/2024.

Dated: 06-11-2024.

Copy submitted to the Chief Development Officer-cum-Executive Officer, Zilla Parishad, Malkangiri for favour of kind information & necessary action.


Block Development Officer
Khairput

Memo No. 6220/2024.

Dated: 06-11-2024.

Copy forwarded to the DeGM, Collectorate, Malkangiri for kind information. He is requested to upload the tender notice and documents in the District Portal for wide publicity.

Copy to Notice Board of this Office for information of General Public.


Block Development Officer
Khairput

Memo No. 6221/2024.

Dated: 06-11-2024.

Copy forwarded to the Principal, Darwin Memorial Degree College, K-Gumma for information & necessary action.


Block Development Officer
Khairput

OFFICE OF THE PANCHAYAT SAMITI: KHAIRPUT.

DETAILED TENDER CALL NOTICE TENDER CALL NOTICE NO.02/2024-25

1. Sealed tenders in conformity with detailed tender call notice to be eventually drawn in form of the O.P.W.D. F-2 Agreement and will be received up to **as detailed in this Office Tender Call Notice** by the Block Development Officer, Khairput for the works as specified in this Office Tender Call Notice **of Khairput Block** at a tender value of **Rupees as specified in the aforesaid Tender Call Notice** from Government Registered Contractors of State P.W.D.(R&B) / Water Resources / Rural Works / C.P.W.D. / M.I. of Class as **specified therein** & above and will be opened on **as detailed in this Office Tender Call Notice** in presence of the tenderers or their authorized agents by the Block Development Officer, Khairput.
2. The tenderers shall pledge note that the work shall have to be completed within such **as specified in the aforesaid Tender Call** Calendar months commencing from the date of issue of the written work order, which will be specified in the said work order. The Tenderers are required to submit a detail programme of work along with tenders which they consider necessary keeping in view the clause of the F-2 Agreement of P.W.D. Without this programme of work, the tender shall be considering defective & liable for rejection. No late tenders will be considered. Tenders submitted through telephone or telegram will not be accepted.
3. The Tenderers are required to pay earnest money @ 01% (one percent) of the estimated amount as mentioned in the tender call notice in shape of fixed deposit (01 year or above) drawn in any Nationalized Bank having its Branch at Malkangiri District or Post Office Account / N.S.C. / POTDR Account / Kishan Bikash Patra duly pledged in favour of Block Development Officer, Khairput, failing which the tender will be summarily rejected. The earnest money shall be refunded to the unsuccessful tenderers after acceptance of the tender on application and the same shall be retained in case of the successful tenderers.
4. The Contractors may obtain a set of tender documents from the office of the Block Development Officer, Khairput on payment of **requisite amount as specified in the aforesaid Tender Call Notice** only in shape of Bank Draft only drawn in favour of Block Development Officer, Khairput per set (non refundable).
5. The Block Development Officer, Khairput reserves the right to reject any or all the tenders received without assigning any reason. The tenderer, whose tender is selected for acceptance shall within a period of seven days upon written intimation being given to his of acceptance of his tender mark an Initially Security Deposit(I.S.D.) equal to that of E.M.D. over and above the E.M.D. as stipulated in clause above and sign the agreement in the item rate contract from the P.W.D. The I.S.D. with the E.M.D. and the amount withheld from successive work bills according to the provisions of the item rate contract shall be retained as Security Deposit. Failure to execute required agreement and deposit of the Security as above shall be entitled for forfeiture of the E.M.D. No tender shall be finally accepted unless the required amount of I.S.D.is deposited. The written agreement to be entered into between the contractor and the Block Development Officer, Khairput shall be the foundation of the right of both the parties and the contract shall be deemed to be incomplete until the agreement has first been signed by the contractor and then by the Block Development Officer, Khairput in the manner as laid down in O.P.W.D. code. The Tenderers are required to pay earnest money @ 01% (one percent) of the estimated amount as mentioned in the tender call notice in shape of fixed deposit (01 year or above) drawn in any Nationalized Bank having its Branch at Malkangiri District or Post Office Account / N.S.C. / POTDR Account / Kishan Bikash Patra duly pledged in favour of Block Development Officer, Khairput. The exemption will be allowed to Govt. Agencies or Engineering Contractor or ST/SC contractors.

Contractor.


**Block Development Officer,
Khairput.**

6. Both E.M.D. & I.S.D. shall be refunded to the successful tenderer after completion of the works with due recommendation of the Engineering Officials concerned provided that all defects if pointed out by Engineering Official are rectified. However, the Security Deposit will be refunded only after clearance from the Audit, which is being deducted from time to time in all running bills as well as final bills.
7. Either the rate shall be quoted in words and figures or the specific percentage with less or excess shall be quoted. Otherwise, the tender will be liable for rejection. In case of discrepancy between unit's rates and totals, the unit rate shall prevail. The rates shall be quoted in rupees and paisa. The tender shall be written legibly and free from erasers, over writings, conversion of figures. Corrections, where unavoidable should be made by scoring out, initialing dating and re-writing.
8. The Contractor shall be responsible for payment of royalties or other charges for quarrying materials. All local taxes including State Sales Tax and Income Tax, Labour Cess, ferry and tollage charges, other local taxes shall be paid by the contractor. The same will be deducted from the work bill if the contractor fails to produce the valid receipt in support of the payment of the above said charges/taxes.
9. The tender shall not be considered unless the tenderer encloses true copies of Income Tax Clearance Certificate, Sales Tax & VAT Clearance Certificate and Labour License from the Competent Authority along with his tender and original certificate are to be produced before the Block Development Officer, Khairput at the time of submission of tender papers.
10. If the contractor removes any materials or stock supplied to him from the site of the work with a view to dispose off the same dishonestly or for any other reason without written permission of the Block Development Officer, Khairput, he shall in addition to any other liabilities Civil or Criminal arising out of such removal, liable to pay the penalties equivalent to given times rate of the materials or stock so removed according to the stipulated rate and the penalties so imposed shall be recovered from the Contractor from any sum that may then be immediately due or any time there after becomes due to the contractor or from his Security.
11. The contractor shall be fully liable to indemnify the Block payment of any compensation under workmen compensation Act VIII of 1923 on account of worker employed by him and the full amount of compensation paid shall be recovered from the Contractor.
12. All reinforced cement concrete work shall conform to the detailed standard specification and shall be of proportion as per design with the specification mentioned in the tender schedule. All items of work shall be executed in accordance with the detailed standard specification of ODISHA as followed by State P.W.D. (Roads & Buildings).
13. Shuttering and Centering shall be with seasoned Sal wood planks inner width of which shall be lined with suitable shuttering made of leak proof and tight including false work as directed or alternatively steel shuttering and centering shall be used.
14. For the purpose of the jurisdiction, in the event of dispute if any, the Contractor shall be deemed to have been into within the Block area and it is agreed that neither party to the agreement will be competent to bring any suit with regards to the matter covered by this contract at any place outside the Malkangiri.
15. It is contractor's responsibility to correctly demarcate the lay-out and orientation of the building etc. and fixation of level pillars at site as directed by the Asst. Engineer / Junior Engineer / G.P.T.A. All expenditure in connection with tools and plants, instrumental materials etc. shall be borne by the contractor.
16. After the work is finished, all surplus materials and debris shall be removed, preliminary work such as mixing plates etc., are to be dismantled and all the materials removed from the site and ground up to 30 meters wide from the building etc. should be cleaned and dressed by the Contractor at his own cost. The net rate quoted should be inclusively of all these expenditures. He should return all the unused Departmental materials to Junior Engineer / JE-I&II(RWSS)/TC concerned.

Contractor.


**Block Development Officer,
Khairput.**

17. The Contractor shall not interfere with the execution of water supply or electrical fittings and other works entrusted to any other agency by the Block at the time during the progress of work.
18. The Engineer-in-Charge of work shall have the right to reject the scaffolding and centering etc., made for the work and such structure if found defective in his/ their opinion.
19. The contractor shall at his own cost make water supply for all work and make sanitary arrangements for his labour campus. The Contractors shall also arrange adequate lighting arrangement for night work, wherever at his own cost.
20. Boiling of water arising from any reason whatsoever from the foundation if necessary shall be borne by the Contractor. No payment shall be made for fixing arranges bench-marks. Level pillars profiles and benching and leveling the ground whenever required. The rates quoted shall be for finished items of work inclusive of all incidental items of work.
21. It should be understood clearly that on claim whatsoever shall be entertained as regards extra item of work or extra quantity of any item in excess of the estimate, written order must be obtained from the Block Development Officer, Khairput for such extra item or quantity of work.
22. The Contractor must follow the fair wages clauses as introduced by the State Government.
23. Except as otherwise provided in the contract, all quotation and disputes relating to the meaning of the specification, designs, drawings and instructions contained therein and as to the quality of workmanship of materials used in the work, or as the any other question claim right, matter of any thing whatsoever of any arising out of the execution of failure to execute the same whether arising during the progress of the work or after the completion or abandonment thereof shall be referred to the tender committee. The award of the Tender Committee shall be final, conclusive and binding on all the parties to this contract.
24. The Contractor shall arrange at his own cost, necessary tools and plants as may be required for the efficient execution of the work and the rates quoted should be inclusive of the running and hire charges of such tools and plants.
25. The Contractor shall submit to the Block Office through the Junior Engineer / JE-I&II(RWSS) concerned regarding payment to the laborer both skilled and un-skilled employed by him on the work. In case of non-payment, Contractor has solely responsible in the Labour Court.
26. No part of the contract shall be sublet without prior permission of the Block Development Officer, Khairput or transfer is made through power of attorney authorizing other to receive payment on the contractor's behalf.
27. No tender documents shall be sold to the intending tenderers on the date of opening of the tender.
28. If any further necessary information is required, the Block Development Officer, Khairput will furnish such information but it must be in order and according to instructions.
29. Only such brand of Cement approved by the Zilla Parishad, Malkangiri will be used and the weight of each cement bag being taken as 50Kg. Further that the M.S. or Tor Rod shall be used in the work as per SAIL Brand. The Contractor should purchase and use only such materials, which has not been available with the Block Office, Khairput.
30. No contractor shall be permitted to furnish his tender in his own manuscript papers or latter pads.
31. In the event of delay in the supply of detailed structural designs for unavoidable reasons, reasonable extension of time will be granted on application by the Contractor, but no claim for monetary compensation therefore shall be entertained under any circumstances.
32. Before quoting his rates / percentage, the tenderer can inspect the site of proposed work. He should inspect the quarries and satisfy himself about the quality, availability of materials, medical aids, labour, food stuff etc., and the rates shall be inclusive of all these items, in every case the materials must comply with the relevant specification. The sample of materials in sealed packets should be submitted along with the tender for approval of Block Development Officer, Khairput while executing the work.

Contractor.


**Block Development Officer,
Khairput.**

33. The tenders containing extraneous conditions not covered by the tender call notice are liable for rejection.
34. The Contractor shall have to furnish certificate along with the tender to the effect that he is not related to any Block Office Staff.
35. Tenders shall be deemed valid and hold good till 90 days from the date of obtaining of tenders.
36. After completion of the work, the Contractor shall arrange at his own cost all requisites and equipments for testing for the work of building, roads and culverts etc., if found necessary and bear the entire cost of such test.
37. The Tenderers are required to submit a list of important works executed by them in the State of ODISHA in the prescribed form enclosed herewith accompanied by a certificate from the concerned authority of the work in respect of satisfactory and timely completion of the work.
38. Before executing of the work, the Contractor must erect one transparency board stating a brief note on the work to be executed and payment will be made out of the estimated amount. No running bill will be paid unless transparency board is setup at the work site. Also, after the work is completed necessary correction is to be made if required over the transparency board by the executants as directed by Engineer-in-Charge.
39. The tenderer may at his option quote reasonable rate for each item of work carefully so that rates for one item should not be unworkably low and for other items too high. He should be able to substantiate his rates for any or all items through detailed analysis, if any.
40. The Block Development Officer, Khairput has reserve the rights to reject any or all tenders received without assigning any reason whatsoever. The Block Development Officer, Khairput has also reserves the right to accept any tender without assigning any reasons to other tenders.
41. The Engineer-in-Charge shall have the power to make any alternations in or addition to the original specification, drawing, designs and instructions that may appear to him to be necessary or advisable during the progress of the work. The Contractor shall be bound to carry out the work in accordance with any instruction, which may be issued to the Contractor after being signed by the Engineer-in-Charges and such alteration shall not invalidate the contract and any additional work which the Contractor may be directed to do the manner, above specification as part of the work shall be carried out by the Contractor on the same conditions in all respects on which he agreed to do the main work. The time for the completion of the work shall be extended in the proportion that the additional work bears to the original work and the certificate of the Engineer-in-Charge shall be conclusive as to such proportion and if the additional work included any class of work shall be carried out at the rate entered in the sanctioned schedule of rates of the locality during the period when the work is being carried on and if such mentioned class of work is not entered in the schedule of rate of the District then the Contractor shall within seven days of the date of his receipt of the order to carry out the work, inform the Engineer-in-Charges of the rate which it is his intention to charge for such class of work and if the Engineer-in-Charges does not agree to this rate, he shall notice in writing be at liberty to cancel his order to carry out such class of work and arrange to carry out it in such manner as may be consider advisable provided always that the Contractor shall commence work of any expenditure in regard thereof before the rates shall have been determined as lastly here in before mentioned when and in such case he shall only be entitled to the paid in respect of the determination of the rate as aforesaid according to such rate of determination of the rate as shall be fixed by the Engineer-in-Charge. In the event of dispute, decision of the Block Development Officer, Khairput shall be final.
42. The Tenderers are required to go through each clause of the item rate contract from the Block Office carefully in addition to the clause herein before tendering.

Contractor.


**Block Development Officer,
Khairput.**

43. The rates quoted should be fairly reasonable and the rates containing abnormal superfluous and unworkable are liable for rejection.
44. The item of work not covered by the tender call notice will be paid at the Current Schedule of Rates of the Public Works Departments, and those not covered by S.R. will be paid on actual analysis approved by the Engineer-in-Charges.
45. Standard Public Works Department specification of the Govt. of Odisha will be followed during executing of the work.
46. The time allowed for carrying out of the work as entered in the tender shall be strictly observed by the Contractor and shall be reckoned from the date on which the written order commence work is issued to the contractor. The work shall throughout the stipulated period of the contract be carried on with all due diligence (time being deemed to be the essence of the Contractor on his part) and the Contractor shall pay the compensation amount that equal to 1/3rd percent on the amount of the estimated cost, if the whole works shown by the tender for every day that the whole work remain un-commenced or during the execution of the work the Contractor shall be bound, in all case in which the time allowed for any work exceed on month to complete one fourth to whole of the work before three fourths of such times has lapsed in the event of the Contractor failing to comply with the condition, he shall be liable to pay as compensation an amount equal to one third percent of the said estimate cost of the whole work for every day that the due quantity of work remains in complete provided always that the entire amount for compensation to be paid under provisions of this clause shall not exceed 10 percent on the estimated cost of work as shown in the tender.
47. The measurement will be taken and payment will be made for M.S.Rods and reinforcement grills as per the actual length and weight of M.S. Rods utilized in works. The weight of binding wires and cut pieces will not be considered for payment.
48. The 05% shall be deducted from each payment of bill on gross value towards Security Deposit money.
49. The 02% of each bill shall be deducted on gross value towards Income Tax deposit.
50. No monetary compensation will be entertained on account of natural calamities like cyclone, earth quake, flood and heavy rain fall etc., but suitable extension of time may be granted by on consideration of the application of the Contractor and that too only on valid reasons. No escalation claim will be entertained during the time period and extension period.
51. The earth work for roads will be done & assessed as per the actual pit excavated and measured or by truck measurement or by section measurement on actual level taken or as assessed by the Engineer-in-charges of the works.
52. The rubble stone, boulders, rough stone, soling stones and over size metals measured by volume of closely packed stacks. 1/6 of the volume for voids will normally be deducted from closely packed stacks. For loosely packed stacks percentage of voids will be determined on actual observation and deducted as assessed at site by Engineer-in-Charges.
53. 12 ½ % will be deducted from metal and moorum towards void. The box heaps of 1.50x1.50x0.50m to be measured as one cum. Similar measurement to be adopted for gravel stacks and voids deducted. The rates should be excluding voids.
54. The sand will be measured in box heaps of 1.50x1.50x0.50m being taken as one cubic meter or as directed by the Engineer-in-Charges of the work.
55. The maintaining traffic, cutting trenches from road side lines and watching, providing signals and providing diversion road etc. and maintenance for them till completion of work should be done by the Contractor at his own cost.
56. It is the Contractor's responsibility to correctly demarcate the road alignment, centre line and edge line of the road and formation width metalling width and soling width and fencing line etc., for execution of work as directed by the Assistant Engineer/Junior Engineer/JE-I&II(RWSS) All expenditure in connections with T&P instruments materials etc. required for this purpose shall be borne by the Contractor.

Contractor.


**Block Development Officer,
Khairput.**

57. The quantities of items of work may vary at the time of actual execution of the work. The Contractors should do the work at his tendered rate whatsoever the quantity may be without any extra claim.
58. The compacted thickness as of soling stone and metal including consolidation of bill materials for which no claim for extra payment shall be entertained.
59. Only clean hand broken stone chips or Crusher broken chips shall be allowed for R.C.C. Work as the case may be as stated in Tender Schedule or as directed by Engineer-in-Charges.
60. Five percent will be deducted for voids of chips of size 6mm and above.
61. The Contractor shall sign on the plan and documents for service connection (Such as P.H.D. and Electric) as and where required by the Department or house owner otherwise the Security money of the contractor will not be released.
62. If the Contractor quotes abnormal low rates for any item and the Department decides to accept his tender, the Department would have discretion of withholding the differential cost; between such highly low rates items and schedule of rates from their first, payment due against other items till such low rate items are executed.
63. No excess over and above the estimated rates shall be allowed. In case, the lowest tenderer fails to negotiate his rates to estimated rates, the documents shall be forwarded to the Collector for approval.
64. For quoting abnormal low rates, the lowest tender may be asked to justify his rates by producing analysis of rates etc. Depending on the type of works, it will be decided by the Tender Committee, whether works can be executed with such low rates. The decision of the Tender Committee in this aspect is conclusive.
65. No empty Cement Bags will be taken back by the Block and the same will be recovered from the bill @Rs.6.00 / per bags.

Contractor.

**Block Development Officer,
Khairput.**

CERTIFICATE NO.-1

(Clause No. 40)

Certified that I/we am/are not related to any way to the Officer of the rank of Asst. Executive Engineer / Junior Engineer / JE-I&II(RWSS) level of Panchayat Samiti, Khairput.

Signature of the Contractor.

CERTIFICATE NO.:-2

(Clause No. 43)

Certified that I/we have executed the following important works details of which are given as per the proforma below:

Sl. No.	Name of the Work	Location	Tender value of the work	Time of completion	Name of Organization etc. in which jurisdiction the work accepted.
01.	02.	03.	04.	05.	06.
01.					
02.					
03.					

Signature of the Contractor.

TENDER SCHEDULE

NAME OF THE WORK : Construction of Multipurpose Class room at Darwin Degree college K.G

SCHEME :	CLASS OF CONTRACTOR : 'B'
AMOUNT PUT TO TENDER (APPROX.) :Rs.-4189552.00	At: Khairput Block
COST OF TENDER PAPER : Rs.6,000.00	DIST : MALKANGIRI
EARNEST MONEY 1% : Rs-41896.00	TIME OF COMPLETION OF THE WORK : 6 (Months)

Sl. No.	Items of Work	Unit	Quantity	Rate per Unit	Amount	
1	Earth work excavation in foundation in hard soil within initial lead and lift etc. complete.	Cum.	70.12	270.90	Rs.	18997.00
2	Filling foundation and plinth with sand well waterd and rammed etc. complete including all cost and conveyance.	Cum.	196.41	668.66	Rs.	131334.00
3	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.	Cum.	90.087	6067.05	Rs.	546563.00
4	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper	Cum.	28.13	6067.05	Rs.	170690.00
5	R.C.C M-20 with 20 mm & downgrade size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete (excluding the cost of Steel but including the cost of centering and shuttering)					
a)	Column footing	Cum.	11.14	6910.85	Rs.	76970.00
b)	Plinth beam	Cum.	7.96	7777.13	Rs.	61921.00
c)	Column	Cum.	15.70	14812.84	Rs.	232502.00
d)	lintel	Cum.	7.96	14566.03	Rs.	115973.00
e)	Roof beam	Cum.	20.57	14812.84	Rs.	304736.00
f)	Chajja	Cum.	2.03	14089.55	Rs.	28574.00
g)	Roof Slab	Cum.	27.06	14089.55	Rs.	381283.00
6	C.C (1:2:4) with 12 mm size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete	Cum.	11.81	4815.76	Rs.	56872.00
7	Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, labour, tools etc. complete.	Qntl.	100.97	9017.42	Rs.	910489.00
8	Providing and laying CB brick masonry work for super structure over the beam for design thouroughly soaked in water with cement mortar 1:6 including	Cum.	46.000	5603.79	Rs.	257774.00
9	12 mm thick cement plaster in cement mortar (1:6) over the outside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	275.65	190.64	Rs.	52549.00
10	16 mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	237.27	274.07	Rs.	65027.00

1	20 mm thick cement plaster in cement mortar (1:6) over stone masonry surface including , curring etc. complete.	Sqm.	39.34	287.13	Rs.	11295.00
2	Supplying, fitting and fixing of M.S grill for windows and ventilators including cost of labour, material, transportation etc. complete.	Kg.	815.74	133.40	Rs.	108819.00
3	finishing surface of walls with Cement based wall putty (water based) approve make finished smooth surface	Sqm.	524.15	117.58	Rs.	61630.00
4	Fixing tiles in floors, treads and steps on 25 mm thick bed of cement mortar 1:4 joined with neat cement slurry mixed with pigments to match the shades of the tile including rubbing , polishing and cost of precast tiles etc.	Sqm.	239.98	1186.25	Rs.	284673.00
5	Fixing ceramic tiles in dados, skirting and riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing and cost of precast tiles.	Sqm.	42.04	1375.96	Rs.	57844.00
6	Fitting and fixing of M.S grill for doors and windows including labour,etc. complete.	Sqm.	28.85	91.06	Rs.	2627.00
3	Providing two coats of enamel paint over the grill work including cost of all materials, cleaning, brushes, putty etc. complete.	Sqm.	28.85	179.68	Rs.	5183.00
3	Distampering two coats with approved distamper including cost of all labour, material etc. complete.	Sqm.	477.24	84.06	Rs.	40117.00
3	Painting 2 coats weather seal paint over a coat of primer including cost, conveyance of all material, labour, T & P etc. complete.	Sqm.	552.25	183.98	Rs.	101603.00
1	cement concrete (1:2:2) using 6 mm size HG chips including cost of all material labour etc complete.	Sqm.	248.28	406.82	Rs.	101007.00
2	Cost of Sign Board of size (1.5mtrx1.2mtr)	No	1	2500.00	Rs.	2500.00
Total					Rs.	4189552.00

(Rupees Fourty one lakhs eighty nine thousand five houndrad fifty two) only.

Tender schedule for the project: Construction of Multipurpose Class room at Darwin Degree college of K,Gumma GP under Khairput Block is technically approved for Rs-4189552.00 /- (Rupees forty one lakhs eighty nine thousand five Hundred fifty two)only.

No of corrections
No of over writings
No. of Interpolation

30/10/24
Superintending Engineer, RWS&S-cum
Addl. P.D. (Technical)
P. W. Malkangiri
Zilla Parishad, Malkangiri.

My quoted rate is % Excess
(Both in figure and words) over the above amount put to tender.

Note:

- The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
- Strike out which are not applicable.
- Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
- If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
- The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
- The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

TENDER SCHEDULE

NAME OF THE WORK : Construction of Additional Class Room with Toilet at Darwin Degree college K Gumma

SCHEME : I D F 24-25	CLASS OF CONTRACTOR : 'B' & 'C'
AMOUNT PUT TO TENDER (APPROX.) :Rs.3607626.00	At: Khairput Block
COST OF TENDER PAPER : Rs.6,000.00	DIST : MALKANGIRI
EARNEST MONEY 1% : Rs-36076.00	TIME OF COMPLETION OF THE WORK : 6 (Months)

Sl. No.	Items of Work	Unit	Quantity	Rate per Unit	Amount	
1	Earth work excavation in foundation in hard soil within initial lead and lift etc. complete.	Cum.	88.63	270.90	Rs.	24009.00
2	Filling foundation and plinth with sand well waterd and rammed etc. complete including all cost and conveyance.	Cum.	101.84	668.66	Rs.	68099.00
3	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.	Cum.	80.36	5456.52	Rs.	438484.00
5	R.C.C M-20 with 20 mm & downgrade size HGCB chips including hoisting and laying all cost, conveyance, royalty and taxes etc. complete (excluding the cost of Steel but including the cost of centering and shuttering)					
a)	Column footing	Cum.	8.69	6910.85	Rs.	60021.00
b)	Plinth beam	Cum.	8.35	7777.13	Rs.	64911.00
c)	Column	Cum.	10.89	14812.84	Rs.	161270.00
d)	intel	Cum.	8.35	14566.03	Rs.	121573.00
e)	Roof beam	Cum.	18.47	14812.84	Rs.	273588.00
f)	Chajja	Cum.	0.16	14089.55	Rs.	2283.00
g)	Roof Slab	Cum.	25.00	14089.55	Rs.	352238.00
6	Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, labour, tools etc. complete.	Qntl.	86.75	9083.03	Rs.	787953.00
7	Providing and laying CB brick masonry work for super structure over the beam for design thouroughly soaked in water with cement mortar 1:6 including	Cum.	65.73	5603.79	Rs.	368332.00
8	12 mm thick cement plaster in cement mortar (1:6) over the outside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	213.67	190.64	Rs.	40734.00
9	16 mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	326.57	274.07	Rs.	89503.00

10	20 mm thick cement plaster in cement mortar (1:6) over stone masonry surface including , curring etc. complete.	Sqm.	37.86	287.13	Rs.	10871.00
11	Supplying, fitting and fixing of M.S grill for windows and ventilators including cost of labour, material, transportation etc. complete.	Kg.	476.67	133.40	Rs.	63588.00
12	Fitting and fixing of M.S grill for doors and windows including labour,etc. complete.	Sqm.	20.28	91.06	Rs.	1847.00
13	Fixing tiles in floors, treads and steps on 25 mm thick bed of cement mortar 1:4 joined with neat cement slurry mixed with pigments to match the shades of the tile including rubbing , polishing and cost of precast tiles etc.	Sqm.	185.68	1186.25	Rs.	220267.00
14	Fixing ceramic tiles in dados, skirting and riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing and cost of precast tiles.	Sqm.	123.33	1375.96	Rs.	169697.00
15	finishing surface of walls with Cement based wall putty (water based) of approved make finished smooth surface	Sqm.	457.67	117.33		53699.00
16	Providing two coats of enamel paint over the grill work including cost of all materials, cleaning, brushes, putty etc. complete.	Sqm.	16.41	179.68	Rs.	2949.00
17	Distampering two coats with approved distamper including cost of all labour, material etc. complete.	Sqm.	512.25	84.06	Rs.	43060.00
18	Painting 2 coats weather seal paint over a coat of primer including cost, conveyance of all material, labour, T & P etc. complete.	Sqm.	578.10	183.98	Rs.	106359.00
19	cement concrete (1:2:2) using 6 mm size HG chips including cost of all material labour etc complete.	Sqm.	196.83	406.82	Rs.	80072.00
20	Cost of Sign Board of size (1.5mtrx1.2mtr)	No	1	2219.00	Rs.	2219.00
Total					Rs.	3607626.00

(Rupees Thirty six lakhs seven thousand six Hundred twenty six) only.

Tender schedule for the project: Construction of Additional Class Room with Toilet at Darwin Degree college of K.Gumr under Khairput Block is technically approved for Rs.3607626.00 /- (Rupees Thirty six lakhs seven thousand six hundred twenty six)only.

No of corrections
No of over writings
No. of Interpolation

My quoted rate is % Excess
(Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.


 Addl. P.D./Tech. In-charge
 Sub-Intending Engineer, RWS&S-cum
 P. Malkangiri
 Addl. Project Director (Tech)
 Zilla Parishad, Malkangiri.

TENDER SCHEDULE

NAME OF THE WORK : Const of 50 seated Girls Hostel building of Darwin degree college K Gumma

CHEMICAL : I D F

CLASS OF CONTRACTOR : B & C

AMOUNT PUT TO TENDER (APPROX.) : Rs.2510581.00

At: KHAIRPUT BLOCK

COST OF TENDER PAPER : Rs.6,000.00

DIST : MALKANGIRI

EARNEST MONEY 1% : Rs-25106.00

TIME OF COMPLETION OF THE WORK :
6 (Months)

Items of Work	Unit	Quantity	Rate per Unit	Amount	
Earth work excavation in foundation in hard soil within initial lead and lift etc. complete.	Cum.	10.98	270.90	Rs.	2974.00
Filling foundation and plinth with sand well watered and rammed etc. complete including all cost and conveyance.	Cum.	8.11	668.66	Rs.	5423.00
Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.	Cum.	2.48	5460.84	Rs.	13543.00
R.R.H.G stone masonry in cement mortar (1:6) in Foundation and Plinth including all cost, conveyance etc. complete.	Cum.	4.09	4789.11	Rs.	19587.00
R.C.C M-20 with 20 mm & downgrade size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete (excluding the cost of Steel but including the cost of centering and shuttering)					
1) Column footing	Cum.	2.49	6919.57	Rs.	17230.00
2) Plinth beam	Cum.	1.44	7785.85	Rs.	11212.00
3) Column	Cum.	4.78	16062.54	Rs.	76779.00
4) lintel	Cum.	6.47	7581.80	Rs.	49054.00
5) Roof beam	Cum.	6.98	16062.54	Rs.	112117.00
6) Chajja	Cum.	0.84	14098.26	Rs.	11843.00
7) Roof Slab	Cum.	23.66	14098.26	Rs.	333565.00
7 Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, labour, tools etc. complete.	Qntl.	47.66	9083.04	Rs.	432898.00
8 Providing and laying CB brick masonry work for super structure over the beam for design thoroughly soaked in water with cement mortar 1:6 including	Cum.	80.090	5604.94	Rs.	448900.00
9 12 mm thick cement plaster in cement mortar (1:6) over the outside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	236.55	190.73	Rs.	45117.00
10 16 mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	534.38	274.16	Rs.	146506.00
11 20 mm thick cement plaster in cement mortar (1:6) over stone masonry surface including , curring etc. complete.	Sqm.	8.64	287.28	Rs.	2482.00
12 Supplying, fitting and fixing of M.S grill for windows and ventilators including cost of labour, material, transportation etc. complete.	Kg.	1524.25	133.40	Rs.	203335.00

1	Fitting and fixing of M.S grill for doors and windows including labour, etc. complete.	Sqm.	44.70	78.18	Rs.	3495.00
1	Fixing tiles in floors, treads and steps on 25 mm thick bed of cement mortar 1:4 joined with neat cement slurry mixed with pigments to match the shades of the tile including rubbing, polishing and cost of precast tiles etc.	Sqm.	188.67	1186.47	Rs.	223851.00
5	Fixing ceramic tiles in dados, skirting and riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing and cost of precast tiles.	Sqm.	100.23	1376.25	Rs.	137942.00
5	Supplying fitting, fixing of M.S Grill including cost of labour, material, transportation etc.	Kg.	136.50	133.40	Rs.	18209.00
7	Providing two coats of enamel paint over the grill work including cost of all materials, cleaning, brushes, putty etc. complete.	Sqm.	99.31	179.68	Rs.	17844.00
3	Distampering two coats with approved distamper including cost of all labour, material etc. complete.	Sqm.	723.05	84.06	Rs.	60780.00
3	Painting 2 coats weather seal paint over a coat of primer including cost, conveyance of all material, labour, T & P etc. complete.	Sqm.	245.19	183.98	Rs.	45110.00
0	cement concrete (1:2:2) using 6 mm size HG chips including cost of all material labour etc complete.	Sqm.	187.36	407.12	Rs.	76278.00
1	Cost of Sign Board of size (1.5mtrx1.2mtr)	No	1	2500.00	Rs.	2500.00
Total					Rs.	2518574.00

(Rupees Twenty five lakhs eighteen thousand five Hundred seventy four) only.

Tender schedule for the project: Const of 50 seated Girls Hostel building of Darwin degree college K Gumma under Khairput Block is technically approved for Rs.2518574.00/- (Rupees Twenty five lakhs eighteen thousand five Hundred seventy four) only.

No of corrections
No of over writings
No. of Interpolation


 Superintending Engineer, RWSI, Gumma
 Addl P.O. (Technical)
 Z. P. Malkangiri, Malkangiri.

My quoted rate is % Excess % Less
(Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.

TENDER SCHEDULE

NAME OF THE WORK : Construction of Dining hall at Darwine degeree college at K.Gumma.

SCHEME : I D F-24-25

CLASS OF CONTRACTOR : 'C' & 'D'

AMOUNT PUT TO TENDER (APPROX.) :Rs.1677034.00

At: Khairput Block

COST OF TENDER PAPER : Rs.6,000.00

DIST : MALKANGIRI

EARNEST MONEY 1% : Rs-16770.00

TIME OF COMPLETION OF THE WORK : 6 (Months)


Sl. No.	Items of Work	Unit	Quantity	Rate per Unit	Amount	
1	Earth work excavation in foundation in hard soil within initial lead and lift etc. complete.	Cum.	42.67	270.90	Rs.	11559.00
2	Filling foundation and plinth with sand well waterd and rammed etc. complete including all cost and conveyance.	Cum.	35.79	668.80	Rs.	23938.00
3	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.	Cum.	14.92	5451.67	Rs.	81362.00
4	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper	Cum.	22.63	5451.67	Rs.	123397.00
5	R.C.C M-20 with 20 mm & downgrade size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete (excluding the cost of Steel but including the cost of centering and shuttering)					
)	Column footing	Cum.	6.70	6793.22	Rs.	45487.00
)	Plinth beam	Cum.	2.82	7659.50	Rs.	21633.00
)	Column	Cum.	4.72	15936.20	Rs.	75212.00
)	intel	Cum.	2.82	14448.40	Rs.	40807.00
)	Roof beam	Cum.	4.27	15936.20	Rs.	68101.00
)	Chajja	Cum.	0.59	13971.92	Rs.	8299.00
)	Roof Slab	Cum.	17.12	13971.92	Rs.	239195.00
)	C.C (1:2:4) with 12 mm size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete	Cum.	3.90	4815.76	Rs.	0.00
)	Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, labour, tools etc. complete.	Qntl.	38.51	9083.03	Rs.	349787.00
)	Providing and laying CB brick masonry work for super structure over the beam for design thouroughly soaked in water with cement mortar 1:6 including	Cum.	20.045	5603.79	Rs.	112325.00
)	12 mm thick cement plaster in cement mortar (1:6) over the outside wall surface including necessary caffolding, curring etc. complete.	Sqm.	132.61	190.64	Rs.	25280.00
)	.6 mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary caffolding, curring etc. complete.	Sqm.	127.13	274.07	Rs.	34843.00
)	0 mm thick cement plaster in cement mortar (1:6) over stone masonry surface including , curring etc. complete.	Sqm.	26.44	287.13	Rs.	7593.00

12	Supplying, fitting and fixing of M.S grill for windows and ventilators including cost of labour, material, transportation etc. complete.	Kg.	698.79	133.40	Rs.	93218.00
13	Cost of Labour for fitting fixing M S Door and window	Sqm.	21.48	91.06	Rs.	1956.00
14	Fixing tiles in floors, treads and steps on 25 mm thick bed of cement mortar 1:4 joined with neat cement slurry mixed with pigments to match the shades of the tile including rubbing, polishing and cost of precast tiles etc.	Sqm.	129.71	1186.25	Rs.	153874.00
15	Fixing ceramic tiles in dados, skirting and riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing and cost of precast tiles.	Sqm.	10.54	1375.96	Rs.	14497.00
17	finishing surface of walls with Cement based wall putty (water based) of approved make finished smooth surface	Sqm.	126.05	117.58		14821.00
18	Providing two coats of enamel paint over the grill work including cost of all materials, cleaning, brushes, putty etc. complete.	Sqm.	21.96	179.68	Rs.	3946.00
19	Distampering two coats with approved distamper including cost of all labour, material etc. complete.	Sqm.	256.85	84.06	Rs.	21591.00
20	Painting 2 coats weather seal paint over a coat of primer including cost, conveyance of all material, labour, T & P etc. complete.	Sqm.	286.18	183.98	Rs.	52652.00
21	cement concrete (1:2:2) using 6 mm size HG chips including cost of all material labour etc complete.	Sqm.	120.87	406.73	Rs.	49161.00
22	Cost of Sign Board of size (1.5mtrx1.2mtr)	No	1	2500.00	Rs.	2500.00
Total					Rs.	1677034.00

(Rupees Sixteen lakhs seventy seven thousand thirty four) only.

Tender schedule for the project: Construction of Dining hall at Darwine degeree college of K,Gumma GP under Khairput Block is technically approved for Rs.1677034.00 /- (Rupees Sixteen lakhs seventy seven thousand thirty four)only.

No of corrections
No of over writings
No. of Interpolation


 Addl P.O. (Technical)
 Z.P. Malkangiri
 Addl. Project Director (Tech)
 RWS&S cum
 Malkangiri
 Parishad, Malkangiri.

My quoted rate is % Excess
 (Both in figure and words) over the above amount put to tender.

Note:

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
3. The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.