APPROVED TENDER SCHEDULE

CONSTRUCTION OF BT ROAD FROM KOIKONDA PHC TO MV-88 ROAD (1250.00 Mt.)					
	Amount put to tender		:-		28,98,772.00
	Cost of tender paper		:- Rs.		6000.00
	Earnest Money Deposit	1 %	:- Rs.		28988.00
	Class of Contractor		:-		"C" & "B"
	Time period for Completeion		:-03 (Three months)		

SI No.	Item of Work	Quantity	Unit	Rate	Amount
1	Providing compacted moorum sub-base and laying in layers not exceeding 0.225 cum and compacting with PRR including watering with taxes of labour & T & P and materials etc. complete in all respects as per direction of EIC.	357.00	Cum	1002.39	357852.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam (grade-II) specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 of MoRD by manual means.	334.69	Cum	3126.62	1046448.00
3	Providing and applying primer coat with bitumen emulsion (SS) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means as per Technical Specification Clause 502 of of MoSRT&H specifications for Road & Bridge works (4th revision)	4462.50	Sqm	31.70	141461.00
4	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates using VG-30 penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of Type C as per Technical Specification Clause 508 of MoRD by manual means i.e.,without paver finisher.	4462.50	Sqm	209.22	933644.00
5	Providing and applying tack coat with bitumen emulsion (RS) using emulsion pressure distributor at the rate of 0.20 kg/sqm on the prepared bituminous/ granular surface cleaned with mechanical broom as per Clause 503 of of MoSRT & H specifications for Road & Bridge works (4th revision)	4462.50	Sqm	11.62	51854.00
6	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B as per Technical Specification Clause 510 of MoRD with VG-30 gradebitumen laid by manual means I.e., without chips spreader.	4462.50	Sqm	74.46	332278.00
7	Line Marking (manually)		L S		20000.00
8	Cost of Display board with Innagruation board with Painting Charges including all etc, comp.				15235.00
	Total 8 (Nine items) only				2898772.00

Tender schedule for the project   Construction of BT road from RD Road to Kalimela GA College,kalimela via Old RD colony

(1250.00 mt)   **Rs. 2898772.00/-**

Rupees (Twenty nine lakhs Fifty five thousand two hundred eighty two) only.

No of corrections   :-
No of over writings   :-
No. of Interpolation   :-

Superintending Engineer,RWS&S-cum
Add. Project Director (Tech)
D.R.D.A., Malkangiri
Zilla Parishad, Malkangiri.

My quoted rate is .... % Excess .... % Less or Schedule rate.
(Both in figure and words) over the above amount put to tender.

Note:

1   The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.

2   Strike out which are not applicable.

3   Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.

4   If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.

5   The percentage quoted in the tender with out mentioning excess or less will be treated as excess.

6   The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be concidered with out rounding off.