

TENDER SCHEDULE

NAME OF THE WORK : CONST. OF OFFICE BUILDING WITH MARKET COMPLEX FOR GPLF AT GOBINDAPALLY...

SCHEME : MISSION SHAKTI 24-25

CLASS OF CONTRACTOR : 'B' & 'C'

AMOUNT PUT TO TENDER (APPROX.) :RS.2334913.00

AT: KHAIRPUT BLOCK

COST OF TENDER PAPER : RS.6,000.00

DIST : MALKANGIRI

EARNEST MONEY 1% : RS 23349.00

TIME OF COMPLETION OF THE WORK :
6 (MONTHS)

SL. NO	ITEMS OF WORK	UNIT	QUANTITY	RATE PER UNIT	AMOUNT	
1	Earth work excavation in foundation in hard soil within initial lead and lift etc. complete.	Cum.	89.62	276.89	Rs.	24815.00
2	Filling foundation and plinth with sand well waterd and rammed etc. complete including all cost and conveyance.	Cum.	33.65	670.09	Rs.	22549.00
3	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.Excl'd Shuttering	Cum.	45.95	5299.77	Rs.	243524.00
4	Providing and laying P.C.C bed concrete (1:4:8) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.Incl'd Shuttering	Cum.	45.95	5672.78	Rs.	125652.00
5	Providing and laying P.C.C bed concrete (1:3:6) using 40 mm down grade size crusher broken hard granite metal including ramming, compacting to proper thickness, watering, curring etc. complete.					
A	ROAD	Cum.	10.25	5710.55	Rs.	58533.00
6	C.C (1:2:4) with 12 mm size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete					
A	ROAD	Cum.	9.13	8067.32	Rs.	73655.00
6	R.C.C M-20 with 20 mm & downgrade size HGCB chips including hoisting and laying, all cost, conveyance, royalty and taxes etc. complete (excluding the cost of Steel but including the cost of centering and shuttering)					
a)	Column footing	Cum.	8.78	6762.80	Rs.	51736.00
b)	Plinth beam	Cum.	4.87	6752.90	Rs.	32935.00
c)	Column,Wall Beam , Roof Beam	Cum.	9.51	15155.36	Rs.	144127.00
d)	lintel	Cum.	3.01	13555.80	Rs.	40803.00
e)	Chajja	Cum.	0.70	13140.38	Rs.	9198.00
f)	Roof Slab	Cum.	14.79	13140.38	Rs.	194346.00
7	20 mm thick cement plaster in cement mortar (1:4) as grading plaster including , curring etc. complete.	Sqm.	136.34	299.66	Rs.	40856.00
8	Providing and laying CB brick masonry work for super structure over the beam for design thouroughly soaked in water with cement mortar 1:6 including necessary scaffolding, racking out joints, curring etc. complete as per specification and direction of the EIC	Cum.	45.08	5551.74	Rs.	250272.00
9	Cutting, bending, binding and placing in position of reinforcement steel for RCC work including cost of binding wire, steel, labour, tools etc. complete.	Qntl.	40.30	8536.55	Rs.	344023.00
10	Supplying, fitting and fixing of M.S grill and windows including cost of labour, material, transportation etc. complete.	Kg.	1184.57	101.69	Rs.	120459.00
11	6 mm thick cement plaster in cement mortar (1:4) including , curring etc. complete.	Sqm.	24.26	165.75	Rs.	4021.00

12	Fixing tiles in floors, treads and steps on 25 mm thick bed of cement mortar 1:4 joined with neat cement slurry mixed with pigments to match the shades of the tile including rubbing, polishing and cost of precast tiles etc.	Sqm.	115.59	1061.18	Rs.	122662.00
13	Fixing ceramic tiles in dados, skirting and riser of steps on 12mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing, polishing and cost of precast tiles.	Sqm.	24.75	1446.10	Rs.	35791.00
14	12 mm thick cement plaster in cement mortar (1:6) over the outside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	158.03	190.73	Rs.	30141.00
15	16 mm thick cement plaster in cement mortar (1:6) over the inside wall surface including necessary scaffolding, curring etc. complete.	Sqm.	351.12	275.18	Rs.	96621.00
16	Finishing plastered surfaces of walls with wall putty & marking smooth to receive painting.	Sqm.	586.12	103.46	Rs.	60640.00
17	Painting 2 coats weather seal paint over a coat of primer including cost, conveyance of all material, labour, T & P etc. complete.	Sqm.	182.29	187.76	Rs.	34227.00
18	Distempering Two coats with approved distemper including cost of all material and labour etc. over one coat of primer.	Sqm.	586.12	159.39	Rs.	93422.00
19	Providing two coats of enamel paint over the grill work including cost of all materials, cleaning, brushes, putty etc. complete.	Sqm.	65.88	188.63	Rs.	12427.00
20	Supplying fitting, fixing of fully glazed aluminium framed openable window using 15 micron anodized OEL aluminium section 2082 as out section, 9139 as mullion section, 4124 as shutter section frame with tapered clip of section 4125, aluminium angle, rubber beading, friction stay and handle etc. with 5mm black glass including all cost of labour, T & P, hire charges of drilling machine etc. complete.	Sqm.	12.96	5013.75	Rs.	64978.00
21	Cost of Sign Board of size (1.5mtrx1.2mtr)	No	1	2500.00	Rs.	2500.00
Total					Rs.	2334913.00

(Rupees twenty three lakhs thirty four thousand nine hundred thirteen) only.

Tender schedule for the project: Construction of GPLF Building at Gobindapally, under Khairput Block is technically approved for Rs.2334913 /- (Rupees twenty three lakhs thirty four thousand nine hundred thirteen) only.

No of corrections
No of over writings
No. of Interpolation


 Superintending Engineer (RWS&S-cum)
 Addl. Project Director (Tech)
 Shri. Pankaj Malik
 Allahabad, Masanganj.

My quoted rate is % Excess % Less

(Both in figure and words) over the above amount put to tender.

Note:

- The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
- Strike out which are not applicable.
- Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
- If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
- The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
- The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.