

## TENDER SCHEDULE

Name of the Project : CONSTRUCTION OF GPLF OFFICE BUILDING WITH MARKET COMPLEX AT MECCA					
Cost of Tender Paper : 6000.00			Class of Contractor : B & C		
Amount put to Tender (Approx.): 24,88,127.00					
Earnest Money : 1% of the Estimate Cost			Time for completion of the work : 6 (Six) Months		
SL. NO.	ITEM OF WORKS	QUANTITY	UNIT	RATE Rs	AMOUNT in Rs
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil Within initial lead of 50m and 1.5m initial lift Including rough dressing and leveling the bed as directed by the Engineer-in-charge	91.70	cum	276.90	25,392.00
2	Filling in Foundation and Plinth with sand well watered and rammed including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	24.73	cum	885.70	21,901.00
3	Cement Concrete(1:3:6)with 4 Cm. size H.G.C.B metal including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	15.57	cum	6314.10	98,321.00
4	Brick work with Clamp-burnt bricks having crushing strength not less than 35 Kg./Cm <sup>2</sup> in Cement mortar (1:6) in foundation & plinth per cum.	39.51	cum	8859.20	3,50,068.00
5	Brick work with Clamp-burnt bricks having crushing strength not less than 35 Kg./Cm <sup>2</sup> in Cement mortar (1:6) in super structure.	37.41	cum	8892.50	3,32,679.00
6	Brick work with Clamp-burnt bricks having crushing strength not less than 35 Kg./Cm <sup>2</sup> in Cement mortar (1:4) in super structure per cum.	3.30	cum	9152.66	28,374.00
7	RCC work of M 20 grade with 20 mm and down grade black hard granite (Crusher Brocken) chips including hosting and laying & royalty of materials etc. complete as per the direction of Engineer-in-charge	44.20	cum	6566.00	2,90,217.00
8	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel etc. complete.	44.20	Qtl	9072.50	4,01,005.00
9	Rigid smooth centering and shuttering for RCC work including flase work and dismantling them after casting.				
	(a) Column base footings	11.30	sqm	248.70	2,810.00
	(b) Plinth Band	31.65	sqm	248.70	7,884.00
	(c) Lintel Band	39.00	sqm	574.00	22,386.00
	(d) Beam and Column	77.30	sqm	1204.50	93,108.00
	(e) Roof slab, Chajja	178.40	sqm	762.10	1,35,959.00
10	12 mm. thick cement plaster with cement mortar (1:6) over brick work including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	149.80	sqm	196.70	29,466.00
11	16 mm. thick cement plaster with cement mortar (1:6) over brick work including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge	297.90	sqm	282.30	84,097.00
12	6 mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment , watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C	104.10	sqm	218.40	22,735.00
13	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conformaing to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	95.80	sqm	1164.20	1,11,530.00
14	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slury mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	14.82	sqm	1301.20	19,284.00
15	Fixing glazed tiles (30cmx30cm / 40cm x 40cm special plain/printed series ceramic tiles of premium grade having thickness 7 mm to 8mm conforming to IS 13755) in floors treads or steps and landing on 20 mm thick bed of cement mortar 1:4 (1cement 4sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles	8.30	sqm	916.30	7,605.00

