

## Approved Tender Schedule

<b>"Construction of New LAC Building at Kutunipall" under Mathili Block</b>		Amount put to tender - Rs.1495976 /- cost of tender paper - Rs. 6000.00 Earnest Money Deposit @ 1 % Rs 14960 /- Class of Contractor "C" & "D" Time of Completion 6 (Six) months			
Sl. No	Item of Work	Quantity	Unit	Rate (Rs)	Amount (Rs)
1	Supplying all labour, T&P etc. and earth work in excavation of foundations in hard soil including dressing and levelling of the bed and depositing the soil within 50M initial lead & 1.50M initial lift and including transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	29.93	100 cum	27689.23	8288.23
2	Supplying all materials, labour, T&P etc. and filling in foundation and plinths with sand well watered and rammed including transportation of all materials to work site payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	26.46	cum	640.04	16937.50
3	Supplying all materials, labour, T&P etc. and providing Cement concrete (1:4:8) in foundation and up to lowest bed level using hard black hand broken granite metal of size 4cm of approved quality from approved quarry as per approved design including hoisting laying, compacting concrete in layers not exceeding 6" thick watering curing finished smooth providing grooves or beads where necessary including cost, conveyance royalties and taxes of all materials with labour and T&P required for the work complete in all respects including dewatering if required all complete as per specification and direction of Engineer-in-charge.	11.95	cum	5805.20	69354.68
4	Supplying all materials, labour, T&P etc. and providing RCC work (1:1.5:3) in plinth bend, Slab, Chajja etc. Having a minimum compressive strength( in work test) of 150.00 kg/sqcm in 15 c.m. Cubes at 28 days as per I.S. 456 and 516 using 12 mm. to 20 mm. size( 20 mm. not to exceed 25 %) HBCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction of concrete, watering & curing for 04 weeks including centering & shuttering and finishing the exposed surfaces smooth with cost, conveyance, royalty & taxes of all materials and labour with T&P required except cost for reinforcement for the work etc. complete as directed by EIC.				
a)	Column Base	6.55	cum	9053.47	59318.31
b)	Plinth Band	4.64	cum	9487.43	44024.06
c)	Beams & Columns	7.17	cum	17611.10	126310.08
d)	Lintel	2.78	cum	12942.76	36034.58
e)	Chajja	8.50	sqm	1156.90	9833.68
f)	Roof Slab	10.81	cum	14894.32	160933.15
5	Supplying all materials, labour, T&P etc. and cutting, straightening,coiled or bent up uncoated HYSD bars bending, binding, welding, and jointing if necessary and tying the grills and placing in proper position as required for RCC works including cost, conveyance, taxes of HYSD bars and binding wires of 18 to 20 gauge required for the work (Payment will made on weight of HYSD bars only and no separate payment will be made towards the weight of binding wires) as directed by EIC	22.35	Qtl.	9356.73	209094.88

6	Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in F&P using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per. sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of woks with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc., complete in all respect.	11.76	cum	5525.84	649
7	Supplying all materials, labour, T&P etc. and providing Well clamp burnt brick masonry in cement mortar (1:6) in superstructure using C.B.Bricks of 9" size having minimum crushing strength not less than 35 kg. per. sq.cm. including splays cutting, circular moulding, chamfering, corbelling and similar such type of woks with all necessary projections watering and curing after immersing the bricks in water for six hours before use etc. complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc., complete in all respect.	39.06	cum	5614.10	219284.71
8	Supplying, fitting, fixing of M.S.door shutters and M.S windows shutters in proper position including making holes in walls,RCC structures and wood work etc.,making good to the damages to walls, or RCC structures including mending or cutting to sizes or grooves in walls with cost, conveyance, royalties with all T&P labour etc.,complete in all respects as per direction of EIC.	912.87	kg.	110.17	100570.89
9	Supplying, fitting and fixing of vetrified tiles in floors of size 600mm x 600mm of approved make coferring to IS : 13755 laid on 20mm thick CM(1:4) and filling joints with white cement including cost of tiles etc.completee.	77.07	sqm	1244.44	95905.80
10	Fixing of ceramic glazed tiles in dedo skritting and riser of steps on 12mm.thick C.P.(1:3) jointed with neat cement slurry mixed with pigment to match the shade of tiles including cost of tiles etc.	24.75	sqm	1249.82	30933.09
11	Supplying all materials, labour, T&P etc. and providing 2.5Cm.(1") thick Artificial stone flooring with Cement concrete(1:2:4) laid to proper slope with 12mm size hard black crusher broken granite stone chips of approved quality from approved quarry including rounding the corners including watering, curing cost, conveyance, taxes, royalties of all materials and labour with T&P required for the work etc.,complete in all respects in all floors as per direction of EIC.	20.45	Sqm	418.77	8564.95
12	Supplying all materials, labour, T&P etc. and providing 12mm (½")thick Cement Plaster (1:6) finished smooth to outside brick walls after raking out the joint including, watering curing with cost, conveyance, taxes, royalties of all materials and all labour,T&P required for the work etc.,complete in all respects as per direction of EIC.	127.97	sqm.	193.59	24774.26
13	Supplying all materials, labour, T&P etc. and providing 16mm(¾") thick Cement Plaster (1:6) finished smooth to brick walls after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour,T&P required for the work etc.,complete in all respects as per direction of EIC.	291.30	sqm.	278.64	81167.13
14	Supplying all materials, labour, T&P etc. and providing 20mm thick Cement Plaster (1:6) finished smooth to stone work after raking out the joint including, watering curing including cost, conveyance, taxes, royalties of all materials and all labour,T&P required for the work etc.,complete in all respects as per direction of EIC.	29.00	sqm.	291.73	8460.24


6497

15	Supplying all materials, labour, T&P etc. and providing Painting two coats to the MS door, window & grill works over a coat of priming including cost of primer and paint and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	59.81	sqm	188.72	11286.65
16	Finishing wall surface with Acylic putty with any shade two cote over new plaster surface including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete	525.34	sqm	110.18	57884.15
17	Supplying all materials, labour, T&P etc. and providing distempering two coats with approved make & shade of distemper to inner side surface over one coat of cement washing over cement plastering including cost of all material, cost, T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	368.37	sqm	101.53	37401.41
18	Supplying all materials, labour, T&P etc. and providing wall painting 2 (Two) coats with any approved water proofing weather coat with brush to wall surface after cleaning surface including cost of paint, watering, and curing cost T&P and transportation of all materials to work site, payment of royalty, taxes etc. all complete as per specification and direction of Engineer-in-charge.	144.96	sqm	101.02	14643.21
					1495976.21
					1495976.21
Total 18 (Eighteen items) only					1495976.21

say

Tender schedule for the project "Construction of L A C Building at Kutunipali of Mathili Block for Rs. 1495976/- Rupees (Fourteen Lakh Ninetyfive Thousand Nine Hundred Seventysix) Only

- No of corrections
- No of over writings
- No. of Interpolation

  
 Addl. P.D.(Tech.)  
 Zillaparishad, Malkangiri  
 Addl. Project Director (Tech)  
 Zillaparishad, Malkangiri

My quoted rate is ..... % Excess ..... % Less or Schedule rate.  
 (Both in figure and words) over the above amount put to tender.

Signature of Contractor

**Note:**

1. The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
2. Strike out which are not applicable
3. Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
5. The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to one decimal point only. if he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.