

APPROVED TENDER SCHEDULE

Const of Post Mortem Centre with Mortuary at SDH Hospital Mathili		Amount put to tender		:- Rs. 1956093.03	
		Cost of tender paper		:- Rs. 6000.00	
		Earnest Money Deposit		1 % :- Rs. 19561.00	
		Class of Contractor		:- "C" & "D"	
		Time period for Completion		:- 06 (Six months)	
SI No.	Item of Work	Quantity	Unit	Rate	Amount
1	Earth Work in exavation of foundation in hard soil within initial leads of 50m & lifts of 1.5m including dressing and levelling of bed etc. and adding contractor's profit and over head charges, etc. complete in all respect	60.21	cum	276.88	16,670.94
2	Supplying & filling of foundation with course sand well watered and rammed including cost, cost of all labour, carriage, royalty complete in all respect. (As Per A/R Page No-1, Item No-2)	72.04	cum	621.21	44,751.97
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including cost, carriage, royalty, cost of all labour, etc complete and as directed by E.I.C	17.51	cum	6204.41	1,08,639.22
4	R.C.C. M-25 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, centering shuttering etc complete but excluding cost of reinforcement.				
	A) COLOUM BASE FOOTING	8.92	cum	7006.52	62,498.16
	B) COLUMN SUPER STRUCTURE	4.68	cum	18678.28	87,414.35
	C) PLINTH BAND	5.26	cum	7876.83	41,432.13
	D) LINTEL BAND	2.48	cum	14669.85	36,381.23
	E) ROOF BEAM	5.97	cum	18678.28	1,11,509.33
	F) CHAJJA	1.35	sqm	1269.46	1,713.77
	J) ROOF SLAB	12.53	cum	14254.38	1,78,607.38
5	Straightening, cutting, bending bent up or coiled rods, including cranking, hooking, welding or jointing the M.S. rods or tor confirming to I.S. 432 (Plain) and 1785 (Tor) steel and binding, tying the grills, hoisting, lowering and placing in proper position required for R.C.C. works including cost, conveyance and taxes of M.S. rods or tor steel and binding wires of 18 to 20 gauge and cost of all labour etc. complete in all respect.	47.39	Qtl	8281.46	3,92,458.39
6	Brick work with Flyash Bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ±2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.	17.33	cum	5670.26	98,265.61
7	Brick work with Flyash Bricks 25cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ±2 percent in cement mortar (1:6) in Super Structure including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.	17.69	cum	5708.58	1,00,984.78
8	12mm thick C.P.(1:6) on brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.	148.00	sqm	176.80	26,166.40

9	16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.	207.81	sqm	271.35	56,389.24
10	6 mm thick C.P. (1:4) to RCC surfaces finished smooth including closed deep chipping and slurry treatment , watering, curing cost, carriage & royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C. Ref(A/R-2006,P-103,Item no-27)	81.35	sqm	210.98	17,156.89
11	Supplying, fitting and fixing Vitrified tile in floors of approved make conformaimg to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.	61.85	sqm	1134.96	70,197.28
12	Fixing tiles in dados skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	100.83	sqm	1269.02	1,27,955.29
13	Supplying, fitting and fixing Granaite tile in floors of approved make conformaimg to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.	15.85	sqm	1978.09	31,352.73
14	Priming 1 coat with wall primer water bond cement primer including all labour, materials etc. complete.	336.30	sqm	68.73	23,113.90
15	Finishing wall surface with Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete.	188.30	sqm	107.66	20,272.38
16	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.	188.30	sqm	108.92	20,509.64
17	Wall painting two coat with any approved weather coat paint including cost of all materials, labour and T&P require for the work etc. complete as directed by the E.I.C.	148.00	sqm	75.56	11,182.88
18	Supplying of M.S. Door, Window with grills, Grills made out of M.S. Angle frame, M.S. Flat, Sheet etc of approved section & design, electrically welded properly with all necessary locking arrangement, and 1 coat red oxide primer including cost of all materials, labour charges, carriage of materials to site etc. complete.				
	GRILL	275.67	Kg	79.30	21,860.63
	WINDOWS & DOOR	104.59	Kg	85.18	8,908.98
19	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless aquare pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect.	153.41	sqm	360.59	55,318.81
20	Providing and Fixing ISI marked 32mm thick flush door shutters conforming to IS : 2202 (part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak three ply veneering with vertical grains or cross bands and face veneers on both faces of shutters of approved design including cost of all door fittings and fixtures etc. complete	11.16	sqm	10668.61	1,19,061.69
21	Supplying, fitting, fixing of two track UPVC Sliding window track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with 6mm thick glass of approved quality complete with frame. Sutters and all fitting and fixtures	4.32	sqm	4960.97	21,431.39

22	Priming one coat with any approved primer (To Receive Enamel paint) including cost of primer & labour to give an even shade excluding cost of primer. (As per A.R. 93/1)	18.63	sqm	76.01	1,416.07
23	Painting two coats with approved enamel paints of approved colour, shade over a coat of primer including sand papering, polishing the surface, cost, conveyances of all materials and cost of all labour etc, complete as per specification & direction of Engineer-in-charge. (As per A.R. 93/3)	18.63	sqm	188.83	3,517.90
24	25mm thick CC 1:2:2 with 6mm size CB chips for grading concret over roof slab etc. complete.	100.21	sqm	388.72	38,953.63
Total 24 (Twenty four items) only					

Tender schedule for the project **Const of Post Mortem Centre with Mortuary at SDH Hospital Mathill**
 Rupees (Nineteen Lakh Fifty Six Thousand Ninety Three) only.

Rs. 1956093.03/-

No of corrections :-
 No of over writings :-
 No. of Interpolation :-


 Superintending Engineer, RWSSLS-cum
 Project Director (Tech)
 Zilla Panchayat, Malkangiri.

My quoted rate is % Excess % Less of Schedule rate.
 (Both in figure and words) over the above amount put to tender.

Note:

- 1 The contractor should not write any thing excepting quoting of percentage and in any case any thing else regarding tender rate is mentioned, the tenderer is liable for rejection.
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
- 5 The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
- 6 The contractor should write percentage excess or less up to one decimal point only. If he writes the percentage excess or less up to two or more decimal points the first decimal point shall only be considered with out rounding off.